

Estimate Abstract

**OD/346/3305/116239/393151/00105735 : Repair and restoration of road from paramananda gochhayta house to tubewell chhaka podasul
Block : Nilgiri, Gram Panchayat : Jadida
Created By: BABITA BEHERA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	0.09344544	Cubic Meter	240.77592	22.499411785805
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	0.70013288	Cubic Meter	1079.329632	755.6741637215
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hard Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hard Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	0.84171688	Cubic Meter	5940.89708926	5000.553362373
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	0.725618	Cubic Meter	7585.49365962	5504.1707383061
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	1.9323824	Square Meter	216.23489289764	417.84850130128
Total Amount (A) : 11700.746177488				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.120	-	120
2	Display Citizen Board @ Rs.179.25	-	179.25
Additional Components Amount (F) : 299.25			

Grand Total Amount (A + F) : 11999.996177488			
---	--	--	--

BABITA BEHERA
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block