

**Estimate Abstract**

**OD/345/3295/115986/421132/00104019 : CONST OF CC ROAD FROM PANCH CHOWK TO BASTI AT MALPADA  
Length 82 Mtr  
Block : Saintala, Gram Panchayat : Budabahal  
Created By:Gobinda Majhi**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	9.344544	Cubic Meter	240.77592	2249.9411785805
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.2017	Cubic Meter	453.796232	13251.621427994
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.34186816	Cubic Meter	5012.97771876	147090.13131287
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	22.9934925	Square Meter	216.23489289764	4971.9953880802
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	19.06286976	Cubic Meter	6479.52977212	123518.43215197
<b>Total Amount (A) : 291082.12145949</b>				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ 1%	-	2910.8212145949
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.1007	miscellaneous item	1007
<b>Additional Components Amount (F) :</b>			<b>8917.8212145949</b>
<b>Grand Total Amount (A + F) :</b>			<b>299999.94267409</b>

**Gobinda Majhi**  
**JE**  
**Saintala Block**

**Santosh Behera**  
**AEE**  
**Saintala Block**

**PURUSOTTAM MIRDHA**  
**BDO**  
**Saintala Block**