

Estimate Abstract

OD/364/3481/119958/430548/00101965 : CONST OF CC DRAIN AT MUNDIGUDA KANSARI SAHI
Block : Khairaput, Gram Panchayat : Rasbeda
Created By:SAMIR DAS

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	102.6	Cubic Meter	240.77592	24703.609392
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	11.4	Cubic Meter	650.544232	7416.2042448
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	342	Square Meter	216.23489289764	73952.333370993
4	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	74.1	Cubic Meter	5877.3042714	435508.24651074
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	3.417	Cubic Meter	7332.5894758	25055.458238809
6	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	0.9	Quintal	8417.5142856	7575.76285704

Total Amount (A) : 574211.61461438

Additional Components

#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ 1%	-	5742.1161461438
2	Display Citizen Board @ Rs.4712	-	4712
Additional Components Amount (F) : 10454.116146144			

Grand Total Amount (A + F) : 584665.73076053

SAMIR DAS
JE
Khairaput Block

DUSHMANT KUMAR BEHERA
AEE
Khairaput Block

ARPITA MOHANTY
BDO
Khairaput Block