

Estimate Abstract

**OD/363/3475/119867/428844/00071821 : Const. of Paver block road at Harijan Sahi, Tunpar
Block : Laxmipur, Gram Panchayat : Tunpar
Created By:RANJIT KHOSLA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	22.29	Cubic Meter	240.77592	5366.8952568
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	15.75	Cubic Meter	587.318232	9250.262154
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	8.82	Cubic Meter	5551.21698844	48961.733838041
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	56	Square Meter	216.42213566644	12119.639597321
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	0.24	Cubic Meter	7032.08725428	1687.7009410272
6	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	105	Square Meter	624.132	65533.86

Total Amount (A) : 142920.09178719

Additional Components

#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ 1%	-	1429.2009178719
2	Display Citizen Board @ Rs.4500	-	4500
3	Any Other Lumpsum @ Rs.1150	T&P and unforeseen items	1150

Additional Components Amount (F) : 7079.2009178719

Grand Total Amount (A + F) : 149999.29270506

RANJIT KHOSLA
JE
Laxmipur Block

AEE
Laxmipur Block

SABYASACHI BEHERA
BDO
Laxmipur Block