

Estimate Abstract

**OD/354/3382/275074/412616/00073912 : CONSTRUCTION OF BOUNDARY WALL OF MISSION SHAKTI GRUHA
AT RANGEILUNDA**

**Block : Rangeilunda, Gram Panchayat : Rangeilunda
Created By:SUJIT KUMAR SETHI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	12.03464	Cubic Meter	240.77592	2897.6515178688
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.406928	Cubic Meter	905.791432	2180.1747598409
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.406928	Cubic Meter	5485.7288167	13203.754289322
4	Masonry Brick Work : AR0603c (Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	12.636372	Cubic Meter	5068.72897136	64050.344849282
5	R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)			
	1.805196	Cubic Meter	6984.2496061192	12607.939451968
6	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			

1.59	Quintal	8664.0005739	13775.760912501	
7	Masonry Brick Work : AR0603ci (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	8.716123416	Cubic Meter	5102.05897136	44470.175670084
8	Plastering : AR1017 (20mm thick cement Plaster in CM (1:4) over masonry work in inside.) : 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	15.79351	Square Meter	272.694320972	4306.8004852145
9	Plastering : AR1004i (12mm thick cement plaster (1:6) over Brick work in outside.) : 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	38.12832023	Square Meter	173.257627454	6606.0223018562
10	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	45.75286944	Square Meter	248.19167229	11355.48117838
11	Painting : AR0918cb (Finishing wall two coats with weather coat with one coat waterbound Primer) : Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	99.67	Square Meter	160.72822700355	16019.782385444
Total Amount (A) : 191473.88780176				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ 0%	-	0
2	Display Citizen Board @ Rs.2500	-	2500
3	Any Other Lumpsum @ Rs.7945	G.I Grill	7945
Additional Components Amount (F) : 10445			

Grand Total Amount (A + F) : 201918.88780176

SUJIT KUMAR SETHI
JE
Rangeilunda Block

SRI NABIN BHUYAN
AEE
Rangeilunda Block

BISWAJIT RAY
BDO
Rangeilunda Block