

Estimate Abstract

**OD/353/3361/117530/414108/00070855 : Construction of play field with sports infrastructure at Parimala
Block : Nuagada, Gram Panchayat : Parimala
Created By:Prasant kumar mallick**

SI No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Site Clearance : AR1403ii (Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials) : Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, up to a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness and as per direction of Engineer-in-Charge (in area of thorny jungle)			
	3721	Square Meter	9.8183211	36533.9728131
2	Earth Work : AR0103a (Earth work in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m. Initial lead and 1.5m initial lift) : Earth work in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.3m in depth and as per specification approved by the department			
	16.2	Cubic Meter	312.915372	5069.2290264
3	Special items for irrigation works : AR0216 (Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum within an initial lead of 1km from the place of excavation.) : Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete. Per 1 cum.			
	900	Cubic Meter	67.165	60448.5
4	miscellaneous : ARM308 (Excavation, loading & carriage by mechanical means in medium hard rock (can not be scapped or peeled with knife, hanheld specimen can be broken with single moderate blow with pick, crushing strength between 100 to 250 kg/sqcm) in canal, foundation & cut-o) : Excavation, loading & carriage by mechanical means in medium hard rock (can not be scapped or peeled with knife, hanheld specimen can be broken with single moderate blow with pick, crushing strength between 100 to 250 kg/sqcm) in canal, foundation & cut-off trenches of earth dam & other deep cutting by means of Rock Breaker with all lifts, delifts including trimming the bed & slopes to designed finished section loading into & transportation by transport vehicle within 1 KM lead & depositing the excavated materials neatly in specific dump yard as directed by the Engineer-in-charge etc. complete. (Special Items for Irrigation works) .			
	700	Cubic Meter	597.8	418460
5	Earth Work : AR0120 (Excavation of founation in laterite rock or any hard rock (other than granite or disintigrated rock) removed by chiselling including dressing and levelling the bed not exceeding 1.5m in depth and depositing the soil within initial lead of 50m) : Excavation of founation in laterite rock or any hard rock (other than granite or disintigrated rock) removed by chiselling including dressing and levelling the bed not exceeding 1.5m in depth and depositing the soil within initial lead of 50m and as per specification approved by the Department			

31.464	Cubic Meter	2094.19056	65891.61177984
Total Amount (A) : 586403.31361934			

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ Rs.6000	-	6000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.2596.68	Unforseen item	2596.68
Additional Components Amount (F) : 13596.68			

Grand Total Amount (A + F) : 599999.99361934			
---	--	--	--

Prasant kumar mallick
JE
Nuagada Block

Pradiumna kumar dash
AEE
Nuagada Block

Loknath Sabar
BDO
Nuagada Block