

Estimate Abstract

**OD/354/3379/117876/413266/00111377 : Const of Bhoga Mandap at Bhairapur under Badapur GP
Block : Patrapur, Gram Panchayat : Badapur
Created By:RAJALAXMI SINGH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	11.5245	Cubic Meter	240.77592	2774.82209004
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	5.889555	Cubic Meter	771.057432	4541.1851539228
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.54523	Cubic Meter	5657.2898407	14399.103821245
4	Masonry Stone Work : AR0703 (Random rubble H.G. stone of masonry.) : Random rubble H.G. stone of size not less than 0.0025 cum stacked masonry in cement mortar (1:6) in foundation and plinth including watering, curing for seven days with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.7793	Cubic Meter	4428.592602813	21165.572626624
5	R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	2.313735	Cubic Meter	6168.9172364255	14273.239722021
6	R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)			
	0.6877	Cubic Meter	6925.7393615672	4762.8309589498

7	R.C.C. Work : AR0404Ac (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)			
	1.581733	Cubic Meter	14224.670623745	22499.630939708
8	R.C.C. Work : AR0404Ad (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)			
	0.4485	Cubic Meter	12833.201464956	5755.6908570328
9	R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)			
	1.78095	Cubic Meter	12470.801640816	22209.874182211
10	R.C.C. Work : AR0404Af (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Sun sheds & Chajja)			
	1.2825	Square Meter	1094.1117057836	1403.1982626675
11	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	10	Quintal	8664.0005739	86640.005739
12	Masonry Brick Work : AR0603ci (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	6.414378	Cubic Meter	5111.93273136	32789.868849515
13	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			

32.307	Square Meter	245.76646029	7939.977032589	
14	Plastering : AR1004i (12mm thick cement plaster (1:6) over Brick work in outside.) : 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	32.748	Square Meter	171.236617454	5607.6567483836
15	Plastering : AR1026 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces (inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	15.5301	Square Meter	159.779558123	2481.392515606
16	Flooring : AR0802i (2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.			
	9.0872	Square Meter	369.168812154	3354.7108298058
17	Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.			
	1.7	Quintal	15995.592825087	27192.507802648
18	Painting : AR0918ca (Finishing wall two coats with weather coat with one coat oilbound Primer) : Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	32.748	Square Meter	156.85349521701	5136.6382613666
19	Painting : AR0920b (Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat waterbound Primer on new work (Inside)) : Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat waterbound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	32.307	Square Meter	166.58511791701	5381.8654045448
20	Painting : AR0903b (Painting two coats of enamel paint with a coat of red oxide primer over iron surface) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.			
	10.90125	Square Meter	230.34345832053	2511.0316250167
Total Amount (A) : 292820.8034229				

Additional Components

#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ Rs.3000	-	3000
2	Display Citizen Board @ Rs.4179	-	4179
Additional Components Amount (F) : 7179			
Grand Total Amount (A + F) : 299999.8034229			

RAJALAXMI SINGH
JE
Patrapur Block

GHANASHYAMA DAKUA
AEE
Patrapur Block

LAXMAN CHARAN SOREN
BDO
Patrapur Block