

Estimate Abstract

**OD/352/3350/117259/403197/00101150 : Construction Of CC Road at Jankhira Juanga Sahi from Jankhira UP
School Juanga Sahi
Block : Dhenkanal Sadar, Gram Panchayat : Beltikiri
Created By:RASMITA MANJARI PRADHAN**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.925	Cubic Meter	240.77592	704.269566
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.7147125	Cubic Meter	620.708832	13478.513833091
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.4189	Cubic Meter	5483.13813034	139375.3398213
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	74.1	Square Meter	216.39264180804	16034.694757976
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	16.6075	Cubic Meter	6944.68966158	115333.93355469
Total Amount (A) : 284926.75153306				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.3000	-	3000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.7050	Moorum filling , vubrator,	7050
Additional Components Amount (F) :			15050
Grand Total Amount (A + F) :			299976.75153306

RASMITA MANJARI PRADHAN
JE
Dhenkanal Sadar Block

Lipika Moharana
AEE
Dhenkanal Sadar Block

Rahul Mandal
BDO
Dhenkanal Sadar Block