

Estimate Abstract

**OD/347/3318/116503/379870/00104565 : CC ROAD FROM CHHOTANKI RD ROAD TO GP OFFICE
Block : Jharbandh, Gram Panchayat : Chhotanki
Created By: BENUDHAR GARDIA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0110 (Fine dressing of earth work in ordinary or hard soil in road formation) : Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.			
	520.125	Square Meter	4.6662	2427.007275
2	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	9.61875	Cubic Meter	240.77592	2315.9633805
3	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	48.80625	Cubic Meter	564.249832	27538.91836305
4	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	64.8375	Cubic Meter	5526.60056346	358330.96403334
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	52.0125	Cubic Meter	7142.13905002	371480.50733917
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	85.5	Square Meter	216.23489289764	18488.083342748

7	Earth Work : AR0122Ai (Earth work in all kinds of soil within 50m, initial lead and 1.5m, initial lift) : Earth work in all kinds of soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.			
	25.65	Cubic Meter	220.96043508	5667.635159802
Total Amount (A) : 786249.0788936				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ Rs.8000	-	8000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.750.92	-	750.92
Additional Components Amount (F) : 13750.92			

Grand Total Amount (A + F) : 799999.9988936
--

BENUDHAR GARDIA
JE
Jharbandh Block

NAGARJUN PRADHAN
AEE
Jharbandh Block

BDO Jharbandh
BDO
Jharbandh Block