

Estimate Abstract

**OD/352/3350/117274/403368/00100070 : Construction of C C road from Ashok Behera House To PMGSY road
Block : Dhenkanal Sadar, Gram Panchayat : Nadiali
Created By:NIMAIN CHARAN NAIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	6.375	Cubic Meter	240.77592	1534.94649
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	28.475	Cubic Meter	651.958232	18564.5106562
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	31.45	Cubic Meter	5681.06510334	178669.49750004
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	93.5	Square Meter	216.39264180804	20232.712009052
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	22.95	Cubic Meter	7143.25333858	163937.66412041
				Total Amount (A) : 382939.33077571

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.4000	-	4000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.8000	Cess 1% & Others etc	8000
Additional Components Amount (F) : 17000			

Grand Total Amount (A + F) : 399939.33077571		
---	--	--

NIMAIN CHARAN NAIK
JE
Dhenkanal Sadar Block

Ramratan Bhuyan
AEE
Dhenkanal Sadar Block

Rahul Mandal
BDO
Dhenkanal Sadar Block