

Estimate Abstract

**OD/365/3512/120414/390995/00100402 : CONSTRUCTION RETAINING WALL KUNDABAI RD ROAD TO SALABANI VILLAGE AT KUNDABAI
Block : Udala, Gram Panchayat : Kundabai
Created By: UGRASEN MALLIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	34.5111	Cubic Meter	240.77592	8309.441852712
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	6.90222	Cubic Meter	1214.518132	8382.871341053
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	36.6623839296	Cubic Meter	6273.1079598	229987.09245402
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	0.88348416	Cubic Meter	7996.8989776	7065.1335758298
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	108.69651	Square Meter	216.70813962884	23555.418466248
6	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	81.5223825	Square Meter	196.967672374	16057.273927408

Total Amount (A) : 293357.23161727

Additional Components

#	Item Name	Remark	Amount (in Rs.)
1	Display Citizen Board @ Rs.3642.76	-	3642.76
2	Provision for Contingency @ Rs.3000	-	3000

Additional Components Amount (F) : 6642.76

Grand Total Amount (A + F) : 299999.99161727

UGRASEN MALLIK
JE
Udala Block

PRATIKSHYA PUHAN
AEE
Udala Block

Samarjit Kar
BDO
Udala Block