

Estimate Abstract

OD/352/3350/117273/403372/00100086 : Construction of C C road Jenasahupatana Mahanty House to Harijan Sahi
Block : Dhenkanal Sadar, Gram Panchayat : Manipur
Created By:NIMAIN CHARAN NAIK

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	8.025	Cubic Meter	240.77592	1932.226758
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	35.845	Cubic Meter	651.958232	23369.44282604
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	39.59	Cubic Meter	5681.06510334	224913.36744123
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	117.7	Square Meter	216.39264180804	25469.413940806
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	28.89	Cubic Meter	7172.84128858	207223.38482708
Total Amount (A) : 482907.83579315				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.5000	-	5000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.7050	Cess 1% & etc	7050
Additional Components Amount (F) : 17050			
Grand Total Amount (A + F) : 499957.83579315			

NIMAIN CHARAN NAIK
JE
Dhenkanal Sadar Block

Ramratan Bhuyan
AEE
Dhenkanal Sadar Block

Rahul Mandal
BDO
Dhenkanal Sadar Block