

**Estimate Abstract**

**OD/346/3309/116325/393742/00063128 : Const. of cc road from Baida Sahi to Attasa Bandha, Kudei  
Block : Soro, Gram Panchayat : Nischintapur  
Created By:Sanjib Kumar Mohapatra**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.973264	Cubic Meter	240.77592	715.89037500288
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	10.76321568	Cubic Meter	1447.535232	15580.133906415
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	15.7582992	Cubic Meter	6118.11088126	96411.021805671
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	59.0491468	Square Meter	216.23489289764	12768.485933995
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	9.63337536	Cubic Meter	7562.65957962	72853.938450379
				<b>Total Amount (A) : 198329.47047146</b>

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.2000	-	2000
2	Display Citizen Board @ Rs.1127.52	-	1127.52
<b>Additional Components Amount (F) : 3127.52</b>			

<b>Grand Total Amount (A + F) : 201456.99047146</b>			
---	--	--	--

**Sanjib Kumar Mohapatra**  
JE  
Soro Block

**Nirmala Kanta Parida**  
AEE  
Soro Block

**Satyanath Naik**  
BDO  
Soro Block