

Estimate Abstract

**OD/346/3305/116248/393279/00105774 : Construction of cc road from naranpur bhrmhananda house to Sashdar behera land via prafulla das house
Block : Nilgiri, Gram Panchayat : Narenpur
Created By:AJAY SOREN**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1.27103921152	Cubic Meter	240.77592	306.0356355098
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	5.4164941376	Cubic Meter	921.527232	4991.4468497668
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.1946900688	Cubic Meter	6094.34724776	43846.939619277
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	5.6669987088	Cubic Meter	7735.85675312	43839.090231393
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	20.0484674	Square Meter	216.39264180804	4338.3408248884
Total Amount (A) : 97321.853160835				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.1000	-	1000
2	Display Citizen Board @ Rs.1678	-	1678
Additional Components Amount (F) : 2678			

Grand Total Amount (A + F) : 99999.853160835			
---	--	--	--

AJAY SOREN
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block