

**Estimate Abstract**

**OD/362/3458/119564/408421/00102755 : Construction of Protection wall at Pendurapalli Pond  
Block : Banapur, Gram Panchayat : Bheteswar  
Created By:snigdharani jena**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	32.57423088	Cubic Meter	240.77592	7843.0904084244
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	43.99652008	Cubic Meter	1493.237732	65697.263860152
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	43.5721503568	Cubic Meter	6192.6828415	269828.50788181
4	<b>R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	25.291716256	Cubic Meter	6663.7431040415	168537.49979029
5	<b>R.C.C. Work : AR0404Ac (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)			
	3.4574992894848	Cubic Meter	14719.496491361	50892.648660455
6	<b>R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)			

4.672200	Cubic Meter	7420.5652291832	34670.899144486
7	<b>R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) :</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.		
	21.184805484	Quintal	8656.9325535
<b>Total Amount (A) : 780865.34197963</b>			

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Display Citizen Board @ Rs.5000	-	5000
2	Any Other Lumpsum @ 1%	Cess	7808.6534197963
3	Provision for Contingency @ Rs.6300	-	6300
<b>Additional Components Amount (F) : 19108.653419796</b>			

<b>Grand Total Amount (A + F) : 799973.99539943</b>			
---	--	--	--

snigdharani jena  
JE  
Banapur Block

SURESH MALIK  
AEE  
Banapur Block

Sri Bikash Kumar Mohanty  
BDO  
Banapur Block