

Estimate Abstract

**OD/346/3305/116247/393087/00068072 : Development and Restoration of FATTA MOHADEVA Temple
Block : Nilgiri, Gram Panchayat : Narasinghpur
Created By: Bharat Singh**

SI No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Flooring : AR0816a (Fixing Marble Tiles in floor, treads or steps and landing of minimum 16 mm thick, dunguri Variety Up to 0.10 Sqm Above 0.10 Sqm. to 0.40 Sqm on a 25mm thick bed of cement mortar 1:1) : Fixing Marble Tiles in floor, treads or steps and landing of minimum 16 mm thick, dunguri Variety Up to 0.10 Sqm Above 0.10 Sqm. to 0.40 Sqm on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the marble tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.			
	42.8004121	Square Meter	1444.5826030298	61828.730722166
2	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	40.134096	Square Meter	634.059	25447.384775664
3	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	14.35811264209	Cubic Meter	6578.8190205052	94459.424548338
4	R.C.C. Work : AR0410f (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor in ground floor R.C.C. walls and fins including attached pilasters			
	75.64905484	Square Meter	933.26665139824	70600.740091969
5	R.C.C. Work : AR0410a (Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height			
	80.9809902675	Square Meter	662.689943368	53665.287854254

6	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	14.35	Quintal	8651.0132768	124142.04052208
7	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	89.34946025	Square Meter	173.3171852552	15485.796954601
8	Painting : AR0918ca (Finishing wall two coats with weather coat with one coat oilbound Primer) : Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	89.34946025	Square Meter	156.80117233871	14010.100115031
Total Amount (A) : 459639.5055841				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Display Citizen Board @ Rs.1780.83	-	1780.83
2	Provision for Contingency @ Rs.5000	-	5000
Additional Components Amount (F) : 6780.83			

Grand Total Amount (A + F) : 466420.3355841
--

Bharat Singh
JE
Nilgiri Block

Soumya Ranjan Sahoo
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block