

Analysis

OD/367/3527/120669/406266/00015281 : Maint & Imp of Kaithagadia Barapada Sahi road
Block : Nayagarh, Panchayat : Khuntubandha
Created By:Padma Charan Sahoo

Item 1

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work
Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.57	5657	0
LR002 : Female mulia	12.36	Per day	452	5586.72	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	354.13	35413	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	305.25	30525	0

Total Amount (a+b+c)				77181.72	
Total GST (a)				0	
LABOUR CESS @ 1% (+)				771.8172	
Grand Total				77953.5372	
Say For Unit 1 (Grand Total/100)				779.535372	

Item 2

Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	2.5	Per day	452	1130	0
LR025 : Mason	0.18	Per day	552	99.36	0
BRM340 : Cement	2.29	1 Qntl.	554.5	1269.805	355.5454
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	63	30.24	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	762.43	731.9328	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	354.13	169.9824	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	276.01	264.9696	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	305.25	146.52	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	199.5	191.52	0

Total Amount (a+b+c)	4723.89203				
Total GST (a)	355.5454				
LABOUR CESS @ 1% (+)	50.7943743				
Grand Total	5130.2318043				
Say For Unit 1 (Grand Total/1)	5130.2318043				

Item 3
Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	3.2	Per day	452	1446.4	0
LR025 : Mason	0.68	Per day	552	375.36	0
BRM340 : Cement	3.23	1 Qntl.	554.5	1791.035	501.4898
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	276.01	248.409	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	199.5	179.55	0

Total Amount (a+b+c)	6335.64501
Total GST (a)	501.4898
LABOUR CESS @ 1% (+)	68.3713481
Grand Total	6905.5061581
Say For Unit 1 (Grand Total/1)	6905.5061581

Rajat Prabha Muduli
JE
Nayagarh Block

Chandra Sekhar Samantaray
AEE
Nayagarh Block

Padma Charan Sahoo
BDO
Nayagarh Block