

Analysis

OD/370/3557/121269/426471/00016598 : Construction of CC road at Gujarbadi

Block : Rayagada, Panchayat : Kutuli

Created By:SHRI SUJIT KUMAR MISHRA

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	452	11661.6	0
LR001 : Male mulia	25.8	Per day	452	11661.6	0

Total Amount (a+b+c)

23323.2

Total GST (a)

0

LABOUR CESS @ 1% (+)

233.232

Grand Total

23556.432

Say For Unit 1 (Grand Total/100)

235.56432

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	452	5586.72	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	731.71	73171	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	152.25	15225	0
Total Amount (a+b+c)				101176.72	
Total GST (a)					0
LABOUR CESS @ 1% (+)				1011.7672	
Grand Total				102188.4872	
Say For Unit 1 (Grand Total/100)				1021.884872	

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	552	99.36	0
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	2.5	Per day	452	1130	0
BRM340 : Cement	2.29	1 Qntl.	528.46	1210.1734	338.848552
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	950	912	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	60.457	138.44653	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	731.71	351.2208	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	796.81	764.9376	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
-------------------	-----------------	-------------	-------------	---------------	------------

BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	152.25	73.08	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	157.3	151.008	0

Total Amount (a+b+c)	5499.92873
Total GST (a)	338.848552
LABOUR CESS @ 1% (+)	58.38777282
Grand Total	5897.16505482
Say For Unit 1 (Grand Total/1)	5897.16505482

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	3.2	Per day	452	1446.4	0
LR025 : Mason	0.68	Per day	552	375.36	0
BRM340 : Cement	3.23	1 Qntl.	528.46	1706.9258	477.939224
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	60.457	195.27611	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	731.71	329.2695	0

BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	796.81	717.129	0
--	-----	-----------	--------	---------	---

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	152.25	68.5125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	157.3	141.57	0

Total Amount (a+b+c)	6904.79691
Total GST (a)	477.939224
LABOUR CESS @ 1% (+)	73.82736134
Grand Total	7456.56349534
Say For Unit 1 (Grand Total/1)	7456.56349534

BHRAMAR BARA KISHAN
JE
Rayagada Block

RAKESH KUMAR SAHOO
AEE
Rayagada Block

SHRI SUJIT KUMAR MISHRA
BDO
Rayagada Block