

Analysis

OD/370/3557/121249/426525/00016726 : Construction of CC road at Padakapadu(Rev. Village-Eramanda)

**Block : Rayagada, Panchayat : Bada Alubadi
Created By:SHRI SUJIT KUMAR MISHRA**

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	452	11661.6	0
LR001 : Male mulia	25.8	Per day	452	11661.6	0

Total Amount (a+b+c)

23323.2

Total GST (a)

0

LABOUR CESS @ 1% (+)

233.232

Grand Total

23556.432

Say For Unit 1 (Grand Total/100)

235.56432

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	452	5586.72	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	536.41	53641	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	40.25	4025	0

Total Amount (a+b+c)	70446.72				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	704.4672				
Grand Total	71151.1872				
Say For Unit 1 (Grand Total/100)	711.511872				

Item 3
Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	2.5	Per day	452	1130	0
LR025 : Mason	0.18	Per day	552	99.36	0
BRM340 : Cement	2.29	1 Qntl.	528.46	1210.1734	338.848552
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	48.567	111.21843	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	536.41	257.4768	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	40.25	19.32	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	149.5	143.52	0

Total Amount (a+b+c)	4724.10223				
Total GST (a)	338.848552				
LABOUR CESS @ 1% (+)	50.62950782				
Grand Total	5113.58028982				
Say For Unit 1 (Grand Total/1)	5113.58028982				

Item 4

Concrete (AR0307a): Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	1050	945	0
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	3.2	Per day	452	1446.4	0
LR025 : Mason	0.68	Per day	552	375.36	0
BRM340 : Cement	3.23	1 Qntl.	528.46	1706.9258	477.939224
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	341.11	306.999	0
BRM340 : Cement	3.23	1 Qntl.	48.567	156.87141	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	536.41	241.3845	0
---	------	----------	--------	----------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	149.5	134.55	0
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0

Total Amount (a+b+c)	5998.99921
Total GST (a)	477.939224
LABOUR CESS @ 1% (+)	64.76938434
Grand Total	6541.70781834
Say For Unit 1 (Grand Total/1)	6541.70781834

JPN BHATTARAY
JE
Rayagada Block

Tanmaya Kumar Padhy
AEE
Rayagada Block

SHRI SUJIT KUMAR MISHRA
BDO
Rayagada Block