

Analysis

OD/372/3570/121486/418949/00017104 : Improvement/Completion Of Kalyan Mandap at Luhurapali
Block : Sonapur, Panchayat : Rengali
Created By:Admin

Item 1

Painting (AR0918g): Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)

Sub-Item of Work
Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work .(Outside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	452	28.928	0
LR048 : Painter/ Polisher	0.054	Per day	602	32.508	0
Combine :: Painting (AR0901ci)					
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	125.5	10.542	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	602	32.365591397849	0
LR001 : Male mulia	0.053763440860215	Per day	452	24.301075268817	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.36677	0.04584625	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0.36677	0.03080868	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0	0	0

Total Amount (a+b+c)	153.07007159667
Total GST (a)	0
LABOUR CESS @ 1% (+)	1.5307007159667

Grand Total	154.60077231263
Say For Unit 1 (Grand Total/1)	154.60077231263

Smt Supriya Guru
JE
Sonepur Block

Baijayantee Karna
AEE
Sonepur Block

Sri Prateek Kar
BDO
Sonepur Block