

Analysis

OD/368/3534/120839/421700/00016412 : Improvement Of Road From Patelpada To Godfula Basti
Block : Nuapada, Gram Panchayat : Godfula
Created By:Admin

Item 1
Earth Work (AR0102a): Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	21.5	Per day	462	9933	0
LR001 : Male mulia	21.5	Per day	462	9933	0
Total Amount (a+b+c)				19866	
Total GST (a)				0	
LABOUR CESS @ 1% (+)				198.66	
Grand Total				20064.66	
Say For Unit 1 (Grand Total/100)				200.6466	

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	57.43	5743	0

Total Amount (a+b+c)	52758.32				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	527.5832				
Grand Total	53285.9032				
Say For Unit 1 (Grand Total/100)	532.859032				

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	485.67	1112.1843	311.411604
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	276.01	264.9696	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
-------------------	-----------------	-------------	-------------	---------------	------------

BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	57.43	27.5664	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	201.5	193.44	0

Total Amount (a+b+c)	4713.95773
Total GST (a)	311.411604
LABOUR CESS @ 1% (+)	50.25369334
Grand Total	5075.62302734
Say For Unit 1 (Grand Total/1)	5075.62302734

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364
-----------------------------	---------------

Total GST (a)	0
LABOUR CESS @ 1% (+)	21.4093953364
Grand Total	2162.3489289764
Say For Unit 1 (Grand Total/10)	216.23489289764

Item 5

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	485.67	1568.7141	439.239948
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	276.01	248.409	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	57.43	25.8435	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	201.5	181.35	0

Total Amount (a+b+c)	6056.79211				
Total GST (a)	439.239948				
LABOUR CESS @ 1% (+)	64.96032058				
Grand Total	6560.99237858				
Say For Unit 1 (Grand Total/1)	6560.99237858				

**DHANANJAYA KALO
JE
Nuapada Block**

**ARUN SAHU
AEE
Nuapada Block**

**ROHITA BHOI
BDO
Nuapada Block**