

## Analysis

**OD/368/3534/120847/421736/00016856 : Imp.of Road with cc/Gr-ii Metaling from Barpadar chandra patel house to Dungripada**  
**Block : Nuapada, Gram Panchayat : Motanuapada**  
**Created By:ROHITA BHOI**

### Item 1

**Earth Work (AR0102a):** Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

**Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	21.5	Per day	452	9718	0
LR001 : Male mulia	21.5	Per day	452	9718	0

**Total Amount (a+b+c)**

19436

**Total GST (a)**

0

**LABOUR CESS @ 1% (+)**

194.36

**Grand Total**

19630.36

**Say For Unit 1 (Grand Total/100)**

196.3036

### Item 2

**Earth Work (AR0115):** Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Filling foundation and plinth with sand well watered and rammed**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	452	5586.72	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	406.21	40621	0

<b>c) Royalty Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM029 : Sand for filling and road blinding</b>	100	1 Cum	57.43	5743	0

<b>Total Amount (a+b+c)</b>	59144.72				
<b>Total GST (a)</b>	0				
<b>LABOUR CESS @ 1% (+)</b>	591.4472				
<b>Grand Total</b>	59736.1672				
<b>Say For Unit 1 (Grand Total/100)</b>	597.361672				

<b>Item 3</b>
---------------

<b>Concrete (AR0303):</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>

<b>a) Specific Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>LR025 : Mason</b>	0.18	Per day	552	99.36	0
<b>LR002 : Female mulia</b>	1.4	Per day	452	632.8	0
<b>LR001 : Male mulia</b>	2.5	Per day	452	1130	0
<b>BRM340 : Cement</b>	2.29	1 Qntl.	546.88	1252.3552	350.659456
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	1 Cum	76.88	36.9024	0
<b>BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)</b>	0.96	1 Cum.	995.25	955.44	0

<b>b) Carriage Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM340 : Cement</b>	2.29	1 Qntl.	48.567	111.21843	0
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	1 Cum	406.21	194.9808	0
<b>BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)</b>	0.96	1 Cum.	380.17	364.9632	0

<b>c) Royalty Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>

<b>BRM340 : Cement</b>	2.29	1 Qntl.	0	0	0
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	1 Cum	57.43	27.5664	0
<b>BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)</b>	0.96	1 Cum.	201.5	193.44	0

<b>Total Amount (a+b+c)</b>	4999.02643
<b>Total GST (a)</b>	350.659456
<b>LABOUR CESS @ 1% (+)</b>	53.49685886
<b>Grand Total</b>	5403.18274486
<b>Say For Unit 1 (Grand Total/1)</b>	5403.18274486

#### Item 4

**R.C.C. Work (AR0410c):** Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

**R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM104 : Non Sal wood scantling &amp; plants(Tentera, Kasi, Gamhari, Kuruma)</b>	0.0267	1Cum.	58374.79	1558.606893	0
<b>BRM092 : Non-sal bullahs 75mm. mean dia of any length.</b>	1.26	1Mtr.	30.81	38.8206	0
<b>LR008 : Sangi mulia</b>	0.5	Per day	502	251	0
<b>LR027 : Carpenter</b>	0.5	Per day	552	276	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM104 : Non Sal wood scantling &amp; plants(Tentera, Kasi, Gamhari, Kuruma)</b>	0.0267	1Cum.	198.296	5.2945032	0
<b>BRM092 : Non-sal bullahs 75mm. mean dia of any length.</b>	0.00614	1Mtr.	198.296	1.21753744	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM104 : Non Sal wood scantling &amp; plants(Tentera, Kasi, Gamhari, Kuruma)</b>	0.0267	1Cum.	0	0	0
<b>BRM092 : Non-sal bullahs 75mm. mean dia of any length.</b>	0.00614	1Mtr.	0	0	0

<b>Total Amount (a+b+c)</b>	2130.93953364
-----------------------------	---------------

<b>Total GST (a)</b>	0
<b>LABOUR CESS @ 1% (+)</b>	21.3093953364
<b>Grand Total</b>	2152.2489289764
<b>Say For Unit 1 (Grand Total/10)</b>	215.22489289764

### Item 5

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002 : Female mulia</b>	1.4	Per day	452	632.8	0
<b>LR001 : Male mulia</b>	3.2	Per day	452	1446.4	0
<b>LR025 : Mason</b>	0.68	Per day	552	375.36	0
<b>BRM340 : Cement</b>	3.23	1 Qntl.	546.88	1766.4224	494.598272
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	1 Cum	76.88	34.596	0
<b>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve &amp; retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</b>	0.9	1 Cum.	1396.62	1256.958	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340 : Cement</b>	3.23	1 Qntl.	48.567	156.87141	0
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	1 Cum	406.21	182.7945	0
<b>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve &amp; retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</b>	0.9	1 Cum.	380.17	342.153	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM340 : Cement</b>	3.23	1 Qntl.	0	0	0
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	1 Cum	57.43	25.8435	0
<b>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve &amp; retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</b>	0.9	1 Cum.	201.5	181.35	0

<b>Total Amount (a+b+c)</b>	6401.54881
<b>Total GST (a)</b>	494.598272
<b>LABOUR CESS @ 1% (+)</b>	68.96147082
<b>Grand Total</b>	6965.1085282
<b>Say For Unit 1 (Grand Total/1)</b>	6965.1085282

## Item 6

**Road Work (AR1307):** Supplying & spreading moorum and consolidation with HRR including cost, conveyance, royalty, taxes cost of all labour & material, hire charges of T & P materials required for work as per specification and complete as per direction of Engineer-in-Charge.

Sub-Item of Work  
**Supplying & spreading moorum and consolidation with HRR**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM025 : Gravel or moorum</b>	3.6224	1 Cum	65.88	238.643712	0
<b>LR002 : Female mulia</b>	1.5	Per day	452	678	0
<b>LR001 : Male mulia</b>	1.5	Per day	452	678	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM025 : Gravel or moorum</b>	3.6224	1 Cum	276.01	999.818624	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM025 : Gravel or moorum</b>	3.6224	1 Cum	40.25	145.8016	0

<b>Total Amount (a+b+c)</b>	2740.263936
<b>Total GST (a)</b>	0
<b>LABOUR CESS @ 1% (+)</b>	27.40263936
<b>Grand Total</b>	2767.66657536

**Say For Unit 1 (Grand Total/2.83)**

977.97405489753

**DHANANJAYA KALO  
JE  
Nuapada Block**

**ARUN SAHU  
AEE  
Nuapada Block**

**ROHITA BHOI  
BDO  
Nuapada Block**