

Analysis

OD/368/3534/120852/421691/00016573 : Repair & Maintance of Bhaismundi Nodal School
Block : Nuapada, Gram Panchayat : Sarabang
Created By:ROHITA BHOI

Item 1
Dismantling (AR1613): Removing old lime or cement plaster from walls including raking out joints 12 mm deep and removing the debris within 50m lead and as per direction of Engineer-in-Charge.
Sub-Item of Work Removing old lime or cement plaster

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	1	Per day	452	452	0
Total Amount (a+b+c)				452	
Total GST (a)					0
LABOUR CESS @ 1% (+)					4.52
Grand Total					456.52
Say For Unit 1 (Grand Total/9.3)					49.088172043011

Item 2
Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.
Sub-Item of Work 16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	452	49.72	0
LR001 : Male mulia	0.13	Per day	452	58.76	0
LR025 : Mason	0.16	Per day	552	88.32	0
BRM340 : Cement	0.043	1 Qntl.	485.67	20.88381	5.8474668
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM340 : Cement	0.043	1 Qntl.	30.732	1.321476	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	341.11	6.13998	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	40.25	0.7245	0

Total Amount (a+b+c)	227.253606
Total GST (a)	5.8474668
LABOUR CESS @ 1% (+)	2.331010728
Grand Total	235.432083528
Say For Unit 1 (Grand Total/1)	235.432083528

Item 3

Dismantling (AR1612): Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.

Sub-Item of Work

Dismantling and removing 2.5 cm. thick artificial stone flooring

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.25	Per day	452	565	0
LR001 : Male mulia	0.75	Per day	452	339	0

Total Amount (a+b+c)	904
Total GST (a)	0
LABOUR CESS @ 1% (+)	9.04
Grand Total	913.04
Say For Unit 1 (Grand Total/9.3)	98.176344086021

Item 4

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified floor tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	485.67	667.79625	186.98295
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	11.2375001	112.375001	0
BRM340 : Cement	1.375	1 Qntl.	30.732	42.2565	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	341.11	51.1665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	40.25	6.0375	0

Total Amount (a+b+c)

14868.663751

Total GST (a)	186.98295
LABOUR CESS @ 1% (+)	150.55646701
Grand Total	15206.20316801
Say For Unit 1 (Grand Total/10)	1520.620316801

Item 5

Painting (AR0918Ai): Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Finishing wall one coat with weather coat

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	194.79	146.0925	0
LR001 : Male mulia	0.43	Per day	462	198.66	0
LR048 : Painter/ Polisher	0.36	Per day	612	220.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0.30732	0.23049	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0	0	0

Total Amount (a+b+c)	565.30299
Total GST (a)	0
LABOUR CESS @ 1% (+)	5.6530299
Grand Total	570.9560199
Say For Unit 1 (Grand Total/10)	57.09560199

Item 6

Painting (AR0922): Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall two coats with distemper of approved shades on new work (Inside)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.52	Per day	612	318.24	0
BRM142 : Distemper	2.5	1 Kg.	70.1	175.25	0
LR001 : Male mulia	0.62	Per day	462	286.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0.30732	0.7683	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0	0	0

Total Amount (a+b+c)	780.6983				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	7.806983				
Grand Total	788.505283				
Say For Unit 1 (Grand Total/10)	78.8505283				

SATYAJEET MOHANTA
JE
Nuapada Block

ARUN SAHU
AEE
Nuapada Block

ROHITA BHOI
BDO
Nuapada Block