

Analysis

OD/370/3557/121267/426467/00016750 : Construction of CC road at Balungi(Revenue village-Punjapai)

Block : Rayagada, Gram Panchayat : Kumbhikota

Created By:SHRI SUJIT KUMAR MISHRA

Item 1

Earth Work (AR0102a): Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	21.5	Per day	452	9718	0
LR001 : Male mulia	21.5	Per day	452	9718	0

Total Amount (a+b+c)

19436

Total GST (a)

0

LABOUR CESS @ 1% (+)

194.36

Grand Total

19630.36

Say For Unit 1 (Grand Total/100)

196.3036

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	452	5586.72	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	666.61	66661	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	152.25	15225	0

Total Amount (a+b+c)				94666.72	
Total GST (a)					0
LABOUR CESS @ 1% (+)				946.6672	
Grand Total				95613.3872	
Say For Unit 1 (Grand Total/100)				956.133872	

Item 3

Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	2.5	Per day	452	1130	0
LR025 : Mason	0.18	Per day	552	99.36	0
BRM340 : Cement	2.29	1 Qntl.	528.46	1210.1734	338.848552
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	48.567	111.21843	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	666.61	319.9728	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
-------------------	-----------------	-------------	-------------	---------------	------------

BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	152.25	73.08	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	157.3	151.008	0

Total Amount (a+b+c)	4847.84623
Total GST (a)	338.848552
LABOUR CESS @ 1% (+)	51.86694782
Grand Total	5238.56172982
Say For Unit 1 (Grand Total/1)	5238.56172982

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	3.2	Per day	452	1446.4	0
LR025 : Mason	0.68	Per day	552	375.36	0
BRM340 : Cement	3.23	1 Qntl.	528.46	1706.9258	477.939224
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	48.567	156.87141	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	666.61	299.9745	0

BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	666.61	599.949	0
--	-----	-----------	--------	---------	---

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	152.25	68.5125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	261.5	235.35	0

Total Amount (a+b+c)	6813.69721
Total GST (a)	477.939224
LABOUR CESS @ 1% (+)	72.91636434
Grand Total	7364.55279834
Say For Unit 1 (Grand Total/1)	7364.55279834

BHRAMAR BARA KISHAN
JE
Rayagada Block

RAKESH KUMAR SAHOO
AEE
Rayagada Block

SHRI SUJIT KUMAR MISHRA
BDO
Rayagada Block