

## Analysis

**OD/367/3530/275505/406814/00017216 : Construction of CC Road from Subash Swain house to Main Road at Giridharapur**  
**Block : Ranapur, Gram Panchayat : Gadabanikilo**  
**Created By:Shri Manoj Kumar Nayak**

### Item 1

**Earth Work (AR0102aa):** Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

**Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

**Total Amount (a+b+c)**

23839.2

**Total GST (a)**

0

**LABOUR CESS @ 1% (+)**

238.392

**Grand Total**

24077.592

**Say For Unit 1 (Grand Total/100)**

240.77592

### Item 2

**Earth Work (AR0115):** Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Filling foundation and plinth with sand well watered and rammed**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.57	5657	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	406.21	40621	0

<b>c) Royalty Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM029 : Sand for filling and road blinding</b>	100	1 Cum	305.25	30525	0

<b>Total Amount (a+b+c)</b>	82513.32				
<b>Total GST (a)</b>	0				
<b>LABOUR CESS @ 1% (+)</b>	825.1332				
<b>Grand Total</b>	83338.4532				
<b>Say For Unit 1 (Grand Total/100)</b>	833.384532				

### Item 3

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

### a) Specific Rate Details

<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>LR002 : Female mulia</b>	1.4	Per day	462	646.8	0
<b>LR001 : Male mulia</b>	3.2	Per day	462	1478.4	0
<b>LR025 : Mason</b>	0.68	Per day	562	382.16	0
<b>BRM340 : Cement</b>	3.23	1 Qntl.	554.5	1791.035	501.4898
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	1 Cum	63	28.35	0
<b>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve &amp; retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</b>	0.9	1 Cum.	1396.62	1256.958	0

### b) Carriage Rate Details

<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM340 : Cement</b>	3.23	1 Qntl.	36.677	118.46671	0
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	1 Cum	796.81	358.5645	0

<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	536.41	482.769	0
--	-----	-----------	--------	---------	---

<b>c) Royalty Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM340</b> : Cement	3.23	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	199.5	179.55	0

<b>Total Amount (a+b+c)</b>	6860.41571				
<b>Total GST (a)</b>	501.4898				
<b>LABOUR CESS @ 1% (+)</b>	73.6190551				
<b>Grand Total</b>	7435.5245651				
<b>Say For Unit 1 (Grand Total/1)</b>	7435.5245651				

<b>Item 4</b>
<b>Concrete (AR0309):</b> Cement Concrete (1:3:6) with 12mm size hard granite (Crusher Broken) chips including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.
Sub-Item of Work <b>Cement Concrete (1:3:6) with 12mm size hard granite (Crusher Broken) chips</b>

<b>a) Specific Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>LR025</b> : Mason	0.68	Per day	562	382.16	0
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	3.2	Per day	462	1478.4	0
<b>BRM340</b> : Cement	2.15	1 Qntl.	554.5	1192.175	333.809
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

<b>b) Carriage Rate Details</b>						
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>	
<b>BRM340 : Cement</b>	2.15	1 Qntl.	36.677	78.85555	0	
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	1 Cum	796.81	358.5645	0	
<b>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve &amp; retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</b>	0.9	1 Cum.	536.41	482.769	0	

<b>c) Royalty Rate Details</b>						
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>	
<b>BRM340 : Cement</b>	2.15	1 Qntl.	0	0	0	
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	1 Cum	305.25	137.3625	0	
<b>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve &amp; retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</b>	0.9	1 Cum.	199.5	179.55	0	

<b>Total Amount (a+b+c)</b>	6221.94455					
<b>Total GST (a)</b>	333.809					
<b>LABOUR CESS @ 1% (+)</b>	65.5575355					
<b>Grand Total</b>	6621.3110855					
<b>Say For Unit 1 (Grand Total/1)</b>	6621.3110855					

<b>Item 5</b>
<b>R.C.C. Work (AR0410c):</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc
Sub-Item of Work <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b>

<b>a) Specific Rate Details</b>						
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>	
<b>BRM104 : Non Sal wood scantling &amp; plants(Tentera, Kasi, Gamhari, Kuruma)</b>	0.0267	1Cum.	58374.79	1558.606893	0	
<b>BRM092 : Non-sal bullahs 75mm. mean dia of any length.</b>	1.26	1Mtr.	30.81	38.8206	0	
<b>LR008 : Sangi mulia</b>	0.5	Per day	512	256	0	

LR027 : Carpenter	0.5	Per day	562	281	0
-------------------	-----	---------	-----	-----	---

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	293.416	7.8342072	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	293.416	1.80157424	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

<b>Total Amount (a+b+c)</b>	2144.06327444
<b>Total GST (a)</b>	0
<b>LABOUR CESS @ 1% (+)</b>	21.4406327444
<b>Grand Total</b>	2165.5039071844
<b>Say For Unit 1 (Grand Total/10)</b>	216.55039071844

**ARATI PRABHA MEKAP**  
**JE**  
**Ranapur Block**

**GYANENDRA PADHI**  
**AEE**  
**Ranapur Block**

**Shri Manoj Kumar Nayak**  
**BDO**  
**Ranapur Block**