

Analysis

**OD/354/3380/117912/411497/00017576 : Repair and Maintenance of Primary School of Raghunath
mandir Sahi Pro PS
Block : Polosara, Gram Panchayat : Kanachai
Created By:SASI BHUSAN MAHAPATRO**

Item 1

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	562.5	773.4375	216.5625
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	66.23	9.9345	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	11.2375001	112.375001	0
BRM340 : Cement	1.375	1 Qntl.	30.732	42.2565	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	341.11	51.1665	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	40.25	6.0375	0

Total Amount (a+b+c)	14972.707501
Total GST (a)	216.5625
LABOUR CESS @ 1% (+)	151.89270001
Grand Total	15341.16270101
Say For Unit 1 (Grand Total/10)	1534.116270101

Item 2

Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work

Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2017.18	153.30568	0
BRM340 : Cement	1.074	1 Qntl.	562.5	604.125	169.155
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	66.23	13.9083	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
-------------------	-----------------	-------------	-------------	---------------	------------

BRM174 : White Cement.	0.076	1Qntl	30.732	2.335632	0
BRM340 : Cement	1.074	1 Qntl.	30.732	33.006168	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	341.11	71.6331	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	11.2375001	112.375001	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	40.25	8.4525	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)	9829.781381
Total GST (a)	169.155
LABOUR CESS @ 1% (+)	99.98936381
Grand Total	10098.92574481
Say For Unit 1 (Grand Total/10)	1009.892574481

Ramakrushna Sabar
JE
Polosara Block

Laxmi Narayan Pattanayak
AEE
Polosara Block

SASI BHUSAN MAHAPATRO
BDO
Polosara Block