

Analysis

OD/345/3285/115798/420238/00016510 : Improvement Of Nuabandh Tank At Kanakpur
Block : Balangir, Gram Panchayat : Sikachhida
Created By:Admin

Item 1

Special items for irrigation works (AR0216): Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete. Per 1 cum.

Sub-Item of Work

Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0065 : Add for trimming of slope and bed manually.	1	L.S.	1	1	0
BRMMR0102 : Cost of mechanical excavation per cum without supervision charge for item AR0216	1	Cum	25.01	25.01	0
BRMMR0104 : Cost of transportation of loose earth within the initial lead of 1 km, excluding supervision charges -AR0216	1	Cum	40.49	40.49	0

Total Amount (a+b+c)	66.5
Total GST (a)	0
LABOUR CESS @ 1% (+)	0.665
Grand Total	67.165
Say For Unit 1 (Grand Total/1)	67.165

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	510.37	51037	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	101.25	10125	0

Total Amount (a+b+c)	74066.32				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	740.6632				
Grand Total	74806.9832				
Say For Unit 1 (Grand Total/100)	748.069832				

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	541.48	1239.9892	347.196976
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	34.299	78.54471	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	510.37	244.9776	0

BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	338.506	324.96576	0
--	------	--------	---------	-----------	---

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	101.25	48.6	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	248.5	238.56	0

Total Amount (a+b+c)	5070.93967				
Total GST (a)	347.196976				
LABOUR CESS @ 1% (+)	54.18136646				
Grand Total	5472.31801246				
Say For Unit 1 (Grand Total/1)	5472.31801246				

Item 4
R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc
Sub-Item of Work R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	243.9536	6.51356112	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	243.9536	1.497875104	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2142.438929224
Total GST (a)	0
LABOUR CESS @ 1% (+)	21.42438929224
Grand Total	2163.8633185162
Say For Unit 1 (Grand Total/10)	216.38633185162

Item 5

Earth Work (AR0101aa): Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum

Sub-Item of Work

Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	19.2	Per day	462	8870.4	0
LR001 : Male mulia	19.2	Per day	462	8870.4	0

Total Amount (a+b+c)	17740.8
Total GST (a)	0
LABOUR CESS @ 1% (+)	177.408
Grand Total	17918.208
Say For Unit 1 (Grand Total/100)	179.18208

Prabhat Kumar Rath
JE
Balangir Block

Neincy Rani Purty
AEE
Balangir Block

HRUSHIKESH GOND
BDO
Balangir Block