

## Analysis

**OD/355/3389/118117/398012/00015504 : Construction of CC Road at Korua from Canal Bandha to Poramananda House, Vill-Korua, GP-Alipingal  
Block : Jagatsinghpur, Gram Panchayat : Alipingal  
Created By:Sri Ashutosh Mishra**

### Item 1

**Earth Work (AR0101aa):** Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum

Sub-Item of Work

**Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	19.2	Per day	462	8870.4	0
LR001 : Male mulia	19.2	Per day	462	8870.4	0

**Total Amount (a+b+c)**

17740.8

**Total GST (a)**

0

**LABOUR CESS @ 1% (+)**

177.408

**Grand Total**

17918.208

**Say For Unit 1 (Grand Total/100)**

179.18208

### Item 2

**Earth Work (AR0115):** Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Filling foundation and plinth with sand well watered and rammed**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	63.2	6320	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

<b>c) Royalty Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM029 : Sand for filling and road blinding</b>	100	1 Cum	77.25	7725	0

<b>Total Amount (a+b+c)</b>	53866.32				
<b>Total GST (a)</b>	0				
<b>LABOUR CESS @ 1% (+)</b>	538.6632				
<b>Grand Total</b>	54404.9832				
<b>Say For Unit 1 (Grand Total/100)</b>	544.049832				

### Item 3

**Concrete (AR0303):** Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal**

### a) Specific Rate Details

<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>LR025 : Mason</b>	0.18	Per day	562	101.16	0
<b>LR002 : Female mulia</b>	1.4	Per day	462	646.8	0
<b>LR001 : Male mulia</b>	2.5	Per day	462	1155	0
<b>BRM340 : Cement</b>	2.29	1 Qntl.	588.54	1347.7566	377.371848
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	1 Cum	71.71	34.4208	0
<b>BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)</b>	0.96	1 Cum.	940.6	902.976	0

### b) Carriage Rate Details

<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM340 : Cement</b>	2.29	1 Qntl.	24.787	56.76223	0
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	1 Cum	341.11	163.7328	0
<b>BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)</b>	0.96	1 Cum.	1321.91	1269.0336	0

### c) Royalty Rate Details

<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
-------------------	-----------------	-------------	-------------	---------------	------------

<b>BRM340 : Cement</b>	2.29	1 Qntl.	0	0	0
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	1 Cum	77.25	37.08	0
<b>BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)</b>	0.96	1 Cum.	444.5	426.72	0

<b>Total Amount (a+b+c)</b>	6141.44203
<b>Total GST (a)</b>	377.371848
<b>LABOUR CESS @ 1% (+)</b>	65.18813878
<b>Grand Total</b>	6584.00201678
<b>Say For Unit 1 (Grand Total/1)</b>	6584.00201678

#### Item 4

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002 : Female mulia</b>	1.4	Per day	462	646.8	0
<b>LR001 : Male mulia</b>	3.2	Per day	462	1478.4	0
<b>LR025 : Mason</b>	0.68	Per day	562	382.16	0
<b>BRM340 : Cement</b>	3.23	1 Qntl.	588.54	1900.9842	532.275576
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	1 Cum	71.71	32.2695	0
<b>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve &amp; retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</b>	0.9	1 Cum.	1396.62	1256.958	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340 : Cement</b>	3.23	1 Qntl.	24.787	80.06201	0
<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	1 Cum	341.11	153.4995	0

<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1321.91	1189.719	0
--	-----	-----------	---------	----------	---

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	77.25	34.7625	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	444.5	400.05	0

<b>Total Amount (a+b+c)</b>	7555.66471
<b>Total GST (a)</b>	532.275576
<b>LABOUR CESS @ 1% (+)</b>	80.87940286
<b>Grand Total</b>	8168.81968886
<b>Say For Unit 1 (Grand Total/1)</b>	8168.81968886

**Item 5**

**R.C.C. Work (AR0410c):** Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

**R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
<b>LR008</b> : Sangi mulia	0.5	Per day	512	256	0
<b>LR027</b> : Carpenter	0.5	Per day	562	281	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

<b>c) Royalty Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0
<b>Total Amount (a+b+c)</b>	2140.93953364				
<b>Total GST (a)</b>	0				
<b>LABOUR CESS @ 1% (+)</b>	21.4093953364				
<b>Grand Total</b>	2162.3489289764				
<b>Say For Unit 1 (Grand Total/10)</b>	216.23489289764				

**Dipti Ranjan Mohanty**  
**JE**  
**Jagatsinghpur Block**

**Sri Susanta Kumar Rout**  
**AEE**  
**Jagatsinghpur Block**

**Sri Ashutosh Mishra**  
**BDO**  
**Jagatsinghpur Block**