

Analysis

OD/354/3380/117900/411362/00017565 : Repair and Maintenance of Primary School of Madhaba UPS
Block : Polosara, Gram Panchayat : Bartani
Created By:SASI BHUSAN MAHAPATRO

Item 1

Other Building Items. (AR1901A): Supplying, fitting and fixing Vitrified Tile 600mmx600mm Plain (Ivory) of approved make conforming to IS :13755 with application of polymer modified quick set cement based water resistant adhesive conforming to IS :15477 of 3mm thick bed and filling joints with white cement of approved quality including cost of all materials, labour ,T&P,etc. required for the work all complete as per direction of Engineer-in-Charge(for repair work only)

Sub-Item of Work

Supplying, fitting and fixing vitrified tile in floors of size 600mm x 600mm of approved make conforming to IS :13755 with application of polymer modified quick set cement based water resistant adhesive conforming to IS :15477 of 3mm thick bed and fillin

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0
BRM174 : White Cement.	0.076	1Qntl	2017.18	153.30568	0
BRM256 : Adhesive (I.S.I.)	54	1 Kg	217.4	11739.6	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	30.732	2.335632	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	11.2375001	112.375001	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)	20838.256313
Total GST (a)	0
LABOUR CESS @ 1% (+)	208.38256313
Grand Total	21046.63887613
Say For Unit 1 (Grand Total/10)	2104.663887613

Item 2

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	562.5	773.4375	216.5625
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	66.23	9.9345	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	11.2375001	112.375001	0
BRM340 : Cement	1.375	1 Qntl.	30.732	42.2565	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	341.11	51.1665	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	40.25	6.0375	0

Total Amount (a+b+c)	14972.707501
Total GST (a)	216.5625
LABOUR CESS @ 1% (+)	151.89270001
Grand Total	15341.16270101
Say For Unit 1 (Grand Total/10)	1534.116270101

Item 3

Other Building Items. (AR1902): Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.

Sub-Item of Work
cement based wall putty (water based)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0038 : Cement based putty	8	kg	30	240	0
LR001 : Male mulia	0.57	Per day	462	263.34	0
LR025 : Mason	0.5	Per day	562	281	0

Total Amount (a+b+c)	784.34
Total GST (a)	0
LABOUR CESS @ 1% (+)	7.8434
Grand Total	792.1834
Say For Unit 1 (Grand Total/10)	79.21834

Sradhanta Prasad Sahu
JE
Polosara Block

Laxmi Narayan Pattanayak
AEE
Polosara Block

SASI BHUSAN MAHAPATRO
BDO
Polosara Block