

Analysis

OD/348/3323/116622/394785/00016210 : Improvement Of Road From RD Road To Ramesh Samal House, Kalahandia, Betara G.P
Block : Bhadrak, Gram Panchayat : Betara
Created By:Admin

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

LABOUR CESS @ 1% (+)

238.392

Grand Total

24077.592

Say For Unit 1 (Grand Total/100)

240.77592

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	65.7	6570	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	822.85	82285	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	40.25	4025	0

Total Amount (a+b+c)	98590.32				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	985.9032				
Grand Total	99576.2232				
Say For Unit 1 (Grand Total/100)	995.762232				

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	514.14	1177.3806	329.666568
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	68.45	32.856	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	822.85	394.968	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	1110.31	1065.8976	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
-------------------	-----------------	-------------	-------------	---------------	------------

BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	40.25	19.32	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	149.5	143.52	0

Total Amount (a+b+c)	5762.71848				
Total GST (a)	329.666568				
LABOUR CESS @ 1% (+)	60.92385048				
Grand Total	6153.30889848				
Say For Unit 1 (Grand Total/1)	6153.30889848				

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	514.14	1660.6722	464.988216
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	68.45	30.8025	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	822.85	370.2825	0

BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1110.31	999.279	0
--	-----	-----------	---------	---------	---

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	149.5	134.55	0

Total Amount (a+b+c)	7077.28106
Total GST (a)	464.988216
LABOUR CESS @ 1% (+)	75.42269276
Grand Total	7617.69196876
Say For Unit 1 (Grand Total/1)	7617.69196876

Item 5
R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc
Sub-Item of Work R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	245.856	6.5643552	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	245.856	1.50955584	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0
Total Amount (a+b+c)	2142.50140404				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	21.4250140404				
Grand Total	2163.9264180804				
Say For Unit 1 (Grand Total/10)	216.39264180804				

SATYAJIT MOHANTY
JE
Bhadrak Block

TUSHARKANTA MISHRA
AEE
Bhadrak Block

RASMI RANJAN MALLICK
BDO
Bhadrak Block