

Analysis

**OD/367/3527/120674/406250/00014379 : Construction of Lekhanpur VSS Lekhanpur
Block : Nayagarh, Gram Panchayat : Nabaghanapur
Created By:Aishwarya Bhuyan**

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
LABOUR CESS @ 1% (+)					238.392
Grand Total					24077.592
Say For Unit 1 (Grand Total/100)					240.77592

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.57	5657	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	354.13	35413	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	305.25	30525	0

Total Amount (a+b+c)	77305.32
Total GST (a)	0
LABOUR CESS @ 1% (+)	773.0532
Grand Total	78078.3732
Say For Unit 1 (Grand Total/100)	780.783732

Item 3

Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	562.84	1288.9036	360.893008
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	63	30.24	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	762.43	731.9328	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	354.13	169.9824	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	276.01	264.9696	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	305.25	146.52	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	199.5	191.52	0

Total Amount (a+b+c)	4783.79063
Total GST (a)	360.893008
LABOUR CESS @ 1% (+)	51.44683638
Grand Total	5196.13047438
Say For Unit 1 (Grand Total/1)	5196.13047438

Item 4

Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	562.84	378.22848	105.9039744
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	63	17.64	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	354.13	99.1564	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	0.8641	302.435	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	305.25	85.47	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	0.04025	14.0875	0

Total Amount (a+b+c)	4885.386744
Total GST (a)	105.9039744
LABOUR CESS @ 1% (+)	49.912907184
Grand Total	5041.203625584
Say For Unit 1 (Grand Total/1)	5041.203625584

Item 5

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	562.84	378.22848	105.9039744
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	63	17.64	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	354.13	99.1564	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	0.8641	302.435	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	305.25	85.47	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	0.04025	14.0875	0

Total Amount (a+b+c)

4918.386744

Total GST (a)

105.9039744

LABOUR CESS @ 1% (+)

50.242907184

Grand Total

5074.533625584

Say For Unit 1 (Grand Total/1)	5074.533625584
--------------------------------	----------------

Item 6

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work
Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	562.84	1954.912172	547.37540816
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1360.29	734.5566	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	276.01	99.3636	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	276.01	149.0454	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	199.5	71.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	199.5	107.73	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	5433.795789146
Total GST (a)	547.37540816
LABOUR CESS @ 1% (+)	59.81171197306
Grand Total	6040.9829092791
Say For Unit 1 (Grand Total/1)	6040.9829092791

Item 7

R.C.C. Work (AR0404Ab): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0

LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	562.84	1954.912172	547.37540816
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1360.29	734.5566	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
LR008 : Sangi mulia	0.25	Per day	512	128	0
LR027 : Carpenter	0.25	Per day	562	140.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	276.01	99.3636	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	276.01	149.0454	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	198.296	2.6472516	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	198.296	0.60876872	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	199.5	71.82	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	199.5	107.73	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

Total Amount (a+b+c)	6183.12462592
Total GST (a)	547.37540816
LABOUR CESS @ 1% (+)	67.3050003408
Grand Total	6797.8050344208
Say For Unit 1 (Grand Total/1)	6797.8050344208

Item 8

R.C.C. Work (AR0404Ac): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	562.84	1954.912172	547.37540816
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1360.29	734.5566	0
Combine :: R.C.C. Work (AR0410d)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0

BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
LR008 : Sangi mulia	5.23875	Per day	512	2682.24	0
LR027 : Carpenter	5.23875	Per day	562	2944.1775	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	276.01	99.3636	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	276.01	149.0454	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	198.296	8.990542344	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	198.296	8.235034584	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	199.5	71.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	199.5	107.73	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

Total Amount (a+b+c)	13409.789241938
Total GST (a)	547.37540816
LABOUR CESS @ 1% (+)	139.57164650098
Grand Total	14096.736296599
Say For Unit 1 (Grand Total/1)	14096.736296599

Item 9

R.C.C. Work (AR0404Bd): Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)(Nominal mix as per IS-456, Table-9).

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Lintels)(Nominal mix as per IS-456, Table-9).

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404B)					
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1360.29	734.5566	0
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	562.84	1954.912172	547.37540816
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
Combine :: R.C.C. Work (AR0410e)					
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	1Mtr.	41.81	157.602795	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	58374.79	4327.527494465	0
LR008 : Sangi mulia	2.24375	Per day	512	1148.8	0
LR027 : Carpenter	2.24375	Per day	562	1260.9875	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	276.01	99.3636	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	276.01	149.0454	0
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0

BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.049542	1Mtr.	198.296	9.823980432	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	198.296	14.700376516	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	199.5	71.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	199.5	107.73	0
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.049542	1Mtr.	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	0	0	0

Total Amount (a+b+c)	12032.097005513
Total GST (a)	547.37540816
LABOUR CESS @ 1% (+)	125.79472413673
Grand Total	12705.26713781
Say For Unit 1 (Grand Total/1)	12705.26713781

Item 10

R.C.C. Work (AR0404Af): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Sun sheds & Chajja)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.025	per hour	700	17.5	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.025	per hour	229.55	5.73875	0
LR001 : Male mulia	0.08333125	Per day	462	38.4990375	0
LR025 : Mason	0.00625	Per day	562	3.5125	0
LR010 : Mate	0.00358125	Per day	512	1.8336	0

BRM340 : Cement	0.21708125	1 Qntl.	562.84	122.18201075	34.21096301
BRM028 : Screened and washed sharp sand for mortar	0.028125	1 Cum	63	1.771875	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.0225	1 Cum.	1418.67	31.920075	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.03375	1 Cum.	1360.29	45.9097875	0
Combine :: R.C.C. Work (AR0410a)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.68432	1Mtr	51.87	35.4956784	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00552344	1Cum.	58374.79	322.4296500776	0
LR008 : Sangi mulia	0.33605	Per day	512	172.0576	0
LR027 : Carpenter	0.33605	Per day	562	188.8601	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.21708125	1 Qntl.	24.787	5.38079294375	0
BRM028 : Screened and washed sharp sand for mortar	0.028125	1 Cum	354.13	9.95990625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.0225	1 Cum.	276.01	6.210225	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.03375	1 Cum.	276.01	9.3153375	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0084318	1Mtr	198.296	1.6719922128	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00552344	1Cum.	198.296	1.09527605824	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.21708125	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.028125	1 Cum	305.25	8.58515625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.0225	1 Cum.	199.5	4.48875	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.03375	1 Cum.	199.5	6.733125	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0084318	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00552344	1Cum.	0	0	0

Total Amount (a+b+c)	1041.1512254424
Total GST (a)	34.21096301
LABOUR CESS @ 1% (+)	10.753621884524
Grand Total	1086.1158103369
Say For Unit 1 (Grand Total/1)	1086.1158103369

Item 11

R.C.C. Work (AR0404Ae): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Stairs excluding landing but including railing)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	562.84	1954.912172	547.37540816
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1360.29	734.5566	0
Combine :: R.C.C. Work (AR0410b)					
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	1.17	1Mtr.	41.81	48.9177	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.04806	1Cum.	58374.79	2805.4924074	0
LR008 : Sangi mulia	4.95	Per day	512	2534.4	0
LR027 : Carpenter	4.95	Per day	562	2781.9	0

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0	
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	276.01	99.3636	0	
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	276.01	149.0454	0	
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.01494	1Mtr.	198.296	2.96254224	0	
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.04806	1Cum.	198.296	9.53010576	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.4733	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0	
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	199.5	71.82	0	
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	199.5	107.73	0	
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.01494	1Mtr.	0	0	0	
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.04806	1Cum.	0	0	0	

Total Amount (a+b+c)	13295.8576145					
Total GST (a)	547.37540816					
LABOUR CESS @ 1% (+)	138.4323302266					
Grand Total	13981.665352887					
Say For Unit 1 (Grand Total/1)	13981.665352887					

Item 12
R.C.C. Work (AR0404Bg): Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).
Sub-Item of Work First Floor

a) Specific Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	

Combine :: R.C.C. Work (AR0404B)						
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212		0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1360.29	734.5566		0
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280		0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82		0
LR001 : Male mulia	1.533295	Per day	462	708.38229		0
LR025 : Mason	0.115	Per day	562	64.63		0
LR010 : Mate	0.065895	Per day	512	33.73824		0
BRM340 : Cement	3.4733	1 Qntl.	562.84	1954.912172	547.37540816	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35		0
Combine :: R.C.C. Work (AR0410a)						
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	7.46592	1Mtr	51.87	387.2572704		0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.06026064	1Cum.	58374.79	3517.7022052656		0
LR008 : Sangi mulia	3.6663	Per day	512	1877.1456		0
LR027 : Carpenter	3.6663	Per day	562	2060.4606		0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	276.01	99.3636	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	276.01	149.0454	0
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0919908	1Mtr	198.296	18.2414076768	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.06026064	1Cum.	198.296	11.94944386944	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	199.5	71.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	199.5	107.73	0
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0919908	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.06026064	1Cum.	0	0	0

Total Amount (a+b+c)	13090.639716312
Total GST (a)	547.37540816
LABOUR CESS @ 1% (+)	136.38015124472
Grand Total	13774.395275717
Say For Unit 1 (Grand Total/1)	13774.395275717

Item 13

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6641.93	69740.265	12553.2477

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	24.787	260.2635	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	76478.6085
Total GST (a)	12553.2477

LABOUR CESS @ 1% (+)	890.318562
Grand Total	89922.174762
Say For Unit 1 (Grand Total/10)	8992.2174762

Item 14

Plastering (AR1017): 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
20mm thick cement Plaster in CM (1:4) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.0744	1 Qntl.	562.84	41.875296	11.72508288
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	63	1.323	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0744	1 Qntl.	24.787	1.8441528	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	354.13	7.43673	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0744	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	305.25	6.41025	0

Total Amount (a+b+c)	259.6894288
Total GST (a)	11.72508288
LABOUR CESS @ 1% (+)	2.7141451168
Grand Total	274.1286567968
Say For Unit 1 (Grand Total/1)	274.1286567968

Item 15

Plastering (AR1027): 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.

Sub-Item of Work
6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.12	Per day	462	55.44	0
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0372	1 Qntl.	562.84	20.937648	5.86254144
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	63	0.4725	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	24.787	0.9220764	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	354.13	2.655975	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	305.25	2.289375	0

Total Amount (a+b+c)	184.4975744				
Total GST (a)	5.86254144				
LABOUR CESS @ 1% (+)	1.9036011584				
Grand Total	192.2637169984				
Say For Unit 1 (Grand Total/1)	192.2637169984				

Item 16
Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.
Sub-Item of Work 16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	562.84	24.20212	6.7765936
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	63	1.134	0

b) Carriage Rate Details					
---------------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	24.787	1.065841	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	354.13	6.37434	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	305.25	5.4945	0

Total Amount (a+b+c)	239.070801				
Total GST (a)	6.7765936				
LABOUR CESS @ 1% (+)	2.458473946				
Grand Total	248.305868546				
Say For Unit 1 (Grand Total/1)	248.305868546				

Item 17

Plastering (AR1004): 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	562.84	20.149672	5.64190816
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	63	0.945	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	24.787	0.8873746	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	354.13	5.31195	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	305.25	4.57875	0

Total Amount (a+b+c)	165.9927466				
-----------------------------	-------------	--	--	--	--

Total GST (a)	5.64190816
LABOUR CESS @ 1% (+)	1.7163465476
Grand Total	173.3510013076
Say For Unit 1 (Grand Total/1)	173.3510013076

Item 18

Flooring (AR0802ii): 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.

Sub-Item of Work

2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.14	Per day	462	64.68	0
LR002 : Female mulia	0.22	Per day	462	101.64	0
LR044 : Mason	0.13	Per day	612	79.56	0
BRM340 : Cement	0.0858	1 Qntl.	562.84	48.291672	13.52166816
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	63	0.756	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	1085.19	24.95937	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	24.787	2.1267246	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	354.13	4.24956	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	276.01	6.34823	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	305.25	3.663	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	199.5	4.5885	0

Total Amount (a+b+c)	340.8630566
Total GST (a)	13.52166816
LABOUR CESS @ 1% (+)	3.5438472476
Grand Total	357.9285720076
Say For Unit 1 (Grand Total/1)	357.9285720076

Item 19

Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.24787	0.193636044	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	661.427872044
Total GST (a)	0
LABOUR CESS @ 1% (+)	6.61427872044
Grand Total	668.04215076444
Say For Unit 1 (Grand Total/9.3)	71.83248932951

Item 20

Painting (AR0918f): Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)

Sub-Item of Work

Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	194.79	243.4875	0
LR001 : Male mulia	0.64	Per day	462	295.68	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	0.24787	0.3098375	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	0	0	0

Total Amount (a+b+c)	869.9573375				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	8.699573375				
Grand Total	878.656910875				
Say For Unit 1 (Grand Total/10)	87.8656910875				

Item 21

Painting (AR0922): Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall two coats with distemper of approved shades on new work (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.52	Per day	612	318.24	0
BRM142 : Distemper	2.5	1 Kg.	70.1	175.25	0
LR001 : Male mulia	0.62	Per day	462	286.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0.24787	0.619675	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0	0	0

Total Amount (a+b+c)	780.549675				
Total GST (a)	0				

LABOUR CESS @ 1% (+)	7.80549675
Grand Total	788.35517175
Say For Unit 1 (Grand Total/10)	78.835517175

Item 22

Iron Work (AR1704): Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

Sub-Item of Work
Iron Doors and windows fixing

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6641.93	3374.10044	607.3380792
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR047 : Fitter	1	Per day	612	612	0
LR026 : Black smith	1	Per day	562	562	0
LR046 : Blacksmith	0.75	Per day	612	459	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	24.787	12.591796	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	0	0	0

Total Amount (a+b+c)	7595.192236
Total GST (a)	607.3380792
LABOUR CESS @ 1% (+)	82.025303152
Grand Total	8284.555618352
Say For Unit 1 (Grand Total/0.508)	16308.180351087

Item 23

Painting (AR0901b): Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat in inner surface with primer of approved quality over iron work.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
BRM137 : Red oxide Primer	0.5022	1 Litre	142.7	71.66394	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.5022	1 Litre	0.24787	0.124480314	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.5022	1 Litre	0	0	0

Total Amount (a+b+c)

608.788420314

Total GST (a)

0

LABOUR CESS @ 1% (+)

6.08788420314

Grand Total

614.87630451714

Say For Unit 1 (Grand Total/9.3)

66.11573166851

Item 24

Painting (AR0903i): Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Painting two coats of enamel paint in outer surface paint (outer surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	1.25	Per day	612	765	0
LR001 : Male mulia	1.1	Per day	462	508.2	0
BRM141 : Enamel paint	1.1625	1 Litre	198.98	231.31425	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0.24787	0.288148875	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0	0	0
Total Amount (a+b+c)				1504.802398875	
Total GST (a)				0	
LABOUR CESS @ 1% (+)				15.04802398875	
Grand Total				1519.8504228638	
Say For Unit 1 (Grand Total/9.3)				163.42477665202	

Monalisa Satapathy
JE
Nayagarh Block

Chandra Sekhar Samantaray
AEE
Nayagarh Block

Aishwarya Bhuyan
BDO
Nayagarh Block