

Analysis

**OD/361/3452/119456/385948/00015614 : Repair & Maintenance of AWC at Silisuan-2
Block : Kendujhar Sadar, Gram Panchayat : Kandaraposi
Created By:Binod Chandra Panda**

Item 1
Painting (AR0901dik): Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge(For repair and maintenance).
Sub-Item of Work Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces (outer surface)(For repair and maintenance) .

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	159.03	133.5852	0
LR048 : Painter/ Polisher	0.51	Per day	612	312.12	0
LR001 : Male mulia	0.51	Per day	462	235.62	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	0.60457	0.5078388	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	0	0	0

Total Amount (a+b+c)	681.8330388
Total GST (a)	0
LABOUR CESS @ 1% (+)	6.818330388
Grand Total	688.651369188
Say For Unit 1 (Grand Total/9.3)	74.04853432129

Item 2
Painting (AR0918fk): Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).
Sub-Item of Work Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)(For repair and maintenance) .

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	194.79	243.4875	0
LR001 : Male mulia	0.6528	Per day	462	301.5936	0
LR048 : Painter/ Polisher	0.5508	Per day	612	337.0896	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	0.60457	0.7557125	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	0	0	0

Total Amount (a+b+c)	882.9264125				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	8.829264125				
Grand Total	891.755676625				
Say For Unit 1 (Grand Total/10)	89.1755676625				

Item 3

Painting (AR0922k): Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For Repair and maintenance)

Sub-Item of Work

Finishing wall two coats with distemper of approved shades on new work (Inside)(For repair and maintenance).

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.5304	Per day	612	324.6048	0
BRM142 : Distemper	2.5	1 Kg.	70.1	175.25	0
LR001 : Male mulia	0.6324	Per day	462	292.1688	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0.60457	1.511425	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0	0	0

Total Amount (a+b+c)	793.535025				
-----------------------------	------------	--	--	--	--

Total GST (a)	0
LABOUR CESS @ 1% (+)	7.93535025
Grand Total	801.47037525
Say For Unit 1 (Grand Total/10)	80.147037525

Ranjan Kumar Swain
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block