

Analysis

OD/354/3380/117911/411483/00017573 : Repair and Maintenance of Primary School of D
Chadiapada PS
Block : Polosara, Gram Panchayat : Kalamba
Created By:SASI BHUSAN MAHAPATRO

Item 1

miscellaneous (ARM122): Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.

Sub-Item of Work

Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMM122 : Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting)	1	Sqm	5.12	5.12	0

Total Amount (a+b+c)

5.12

Total GST (a)

0

Grand Total

5.12

Say For Unit 1 (Grand Total/1)

5.12

Item 2

Painting (AR0901di): Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	159.03	133.5852	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	0.30732	0.2581488	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	0	0	0
Total Amount (a+b+c)				670.8433488	
Total GST (a)					0
LABOUR CESS @ 1% (+)				6.708433488	
Grand Total				677.551782288	
Say For Unit 1 (Grand Total/9.3)				72.855030353548	

Item 3

Painting (AR0920k): Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For Repair and maintenance)

Sub-Item of Work

Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)(For Repair and maintenance)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
LR048 : Painter/ Polisher	0.5508	Per day	612	337.0896	0
LR001 : Male mulia	0.6528	Per day	462	301.5936	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.30732	0.38415	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0

Total Amount (a+b+c)				950.74235	
Total GST (a)					0
LABOUR CESS @ 1% (+)				9.5074235	
Grand Total				960.2497735	
Say For Unit 1 (Grand Total/10)				96.02497735	

Sarat Kumar Malla
JE
Polosara Block

Laxmi Narayan Pattanayak
AEE
Polosara Block

SASI BHUSAN MAHAPATRO
BDO
Polosara Block