

Analysis

OD/346/3309/116317/393979/00063520 : Repair and restoration of Kedarpur -4 AWC
Block : Soro, Gram Panchayat : Kedarpur
Created By: Satyanath Naik

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
LABOUR CESS @ 1% (+)					238.392
Grand Total					24077.592
Say For Unit 1 (Grand Total/100)					240.77592

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	907.91	90791	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	442.25	44225	0

Total Amount (a+b+c)	147920.32
Total GST (a)	0
LABOUR CESS @ 1% (+)	1479.2032
Grand Total	149399.5232
Say For Unit 1 (Grand Total/100)	1493.995232

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	521.52	1194.2808	214.970544
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	907.91	435.7968	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	510.37	489.9552	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	552.5	530.4	0

Total Amount (a+b+c)	5814.77743
Total GST (a)	214.970544
LABOUR CESS @ 1% (+)	60.29747974
Grand Total	6090.04545374
Say For Unit 1 (Grand Total/1)	6090.04545374

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	224.9296	6.00562032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	224.9296	1.381067744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2141.814181064
Total GST (a)	0
LABOUR CESS @ 1% (+)	21.41814181064
Grand Total	2163.2323228746
Say For Unit 1 (Grand Total/10)	216.32323228746

Item 5

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0	
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0	
LR044 : Mason	3.25	Per day	612	1989	0	
LR001 : Male mulia	3.25	Per day	462	1501.5	0	
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0	
BRM340 : Cement	1.375	1 Qntl.	521.52	717.09	129.0762	
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0	

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	9.6011111	96.011111	0	
BRM340 : Cement	1.375	1 Qntl.	24.787	34.082125	0	
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	907.91	136.1865	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0	
BRM340 : Cement	1.375	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	442.25	66.3375	0	

Total Amount (a+b+c)	15038.739236					
Total GST (a)	129.0762					
LABOUR CESS @ 1% (+)	151.67815436					
Grand Total	15319.49359036					
Say For Unit 1 (Grand Total/10)	1531.949359036					

Item 6

Painting (AR0919): Finishing wall One Coat with plastic emulsion paint of approved shades on old work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall One Coat with plastic emulsion paint of approved shades on old work (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	0.75	1 Litre	249.34	187.005	0
LR001 : Male mulia	0.43	Per day	462	198.66	0
LR048 : Painter/ Polisher	0.36	Per day	612	220.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	0.75	1 Litre	0.24787	0.1859025	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	0.75	1 Litre	0	0	0

Total Amount (a+b+c)

606.1709025

Total GST (a)

0

LABOUR CESS @ 1% (+)

6.061709025

Grand Total

612.232611525

Say For Unit 1 (Grand Total/10)

61.2232611525

Item 7

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	521.52	1684.5096	303.211728

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	907.91	408.5595	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	510.37	459.333	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	149.5	134.55	0

Total Amount (a+b+c)	6764.94061
Total GST (a)	303.211728
LABOUR CESS @ 1% (+)	70.68152338
Grand Total	7138.83386138
Say For Unit 1 (Grand Total/1)	7138.83386138

Item 8
Painting (AR0901b): Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.
Sub-Item of Work Priming one coat in inner surface with primer of approved quality over iron work.

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
BRM137 : Red oxide Primer	0.5022	1 Litre	142.7	71.66394	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details					
---------------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.5022	1 Litre	0.24787	0.124480314	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.5022	1 Litre	0	0	0

Total Amount (a+b+c)	608.788420314				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	6.08788420314				
Grand Total	614.87630451714				
Say For Unit 1 (Grand Total/9.3)	66.11573166851				

Item 9

Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.24787	0.193636044	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	661.427872044				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	6.61427872044				
Grand Total	668.04215076444				
Say For Unit 1 (Grand Total/9.3)	71.83248932951				

Item 10

Painting (AR0918ca): Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Finishing wall two coats with weather coat with one coat oilbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901ci)					
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	125.5	10.542	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.24787	0.03098375	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0.24787	0.02082108	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0	0	0

Total Amount (a+b+c)	155.30049031387
Total GST (a)	0
LABOUR CESS @ 1% (+)	1.5530049031387
Grand Total	156.85349521701
Say For Unit 1 (Grand Total/1)	156.85349521701

Item 11

Painting (AR0903b): Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Painting two coats of enamel paint with a coat of red oxide primer over iron surface

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0901b)					
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
BRM137 : Red oxide Primer	0.054	1 Litre	142.7	7.7058	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0
Combine :: Painting (AR0903)					
LR048 : Painter/ Polisher	0.13440860215054	Per day	612	82.258064516129	0
LR001 : Male mulia	0.11827956989247	Per day	462	54.645161290323	0
BRM141 : Enamel paint	0.125	1 Litre	205.34	25.6675	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.054	1 Litre	0.24787	0.01338498	0
BRM141 : Enamel paint	0.125	1 Litre	0.24787	0.03098375	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.054	1 Litre	0	0	0
BRM141 : Enamel paint	0.125	1 Litre	0	0	0

Total Amount (a+b+c)	228.06283002032
Total GST (a)	0
LABOUR CESS @ 1% (+)	2.2806283002032
Grand Total	230.34345832053
Say For Unit 1 (Grand Total/1)	230.34345832053

Monalisa Pati
JE
Soro Block

Nirmala Kanta Parida
AEE
Soro Block

Satyanath Naik
BDO
Soro Block