

Analysis

OD/346/3309/116311/393969/00063490 : Completion of AWC building at Ainri Biswal Sahi ,
Malik Sahi
Block : Soro, Gram Panchayat : Antapur
Created By:Satyanath Naik

Item 1

Painting (AR0901b): Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat in inner surface with primer of approved quality over iron work.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
BRM137 : Red oxide Primer	0.5022	1 Litre	142.7	71.66394	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.5022	1 Litre	0.24787	0.124480314	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.5022	1 Litre	0	0	0

Total Amount (a+b+c)

608.788420314

Total GST (a)

0

LABOUR CESS @ 1% (+)

6.08788420314

Grand Total

614.87630451714

Say For Unit 1 (Grand Total/9.3)

66.11573166851

Item 2

Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.24787	0.193636044	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	661.427872044				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	6.61427872044				
Grand Total	668.04215076444				
Say For Unit 1 (Grand Total/9.3)	71.83248932951				

Item 3

Painting (AR0920): Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0
LR001 : Male mulia	0.64	Per day	462	295.68	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.24787	0.3098375	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0

Total Amount (a+b+c)	938.1448375				
Total GST (a)	0				

LABOUR CESS @ 1% (+)	9.381448375
Grand Total	947.526285875
Say For Unit 1 (Grand Total/10)	94.7526285875

Item 4

Painting (AR0903i): Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Painting two coats of enamel paint in outer surface paint (outer surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	1.25	Per day	612	765	0
LR001 : Male mulia	1.1	Per day	462	508.2	0
BRM141 : Enamel paint	1.1625	1 Litre	205.34	238.70775	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0.24787	0.288148875	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0	0	0

Total Amount (a+b+c)	1512.195898875
Total GST (a)	0
LABOUR CESS @ 1% (+)	15.12195898875
Grand Total	1527.3178578638
Say For Unit 1 (Grand Total/9.3)	164.22772665202

Item 5

Painting (AR0918ca): Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Finishing wall two coats with weather coat with one coat oilbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0

LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901ci)					
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	125.5	10.542	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.24787	0.03098375	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0.24787	0.02082108	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0	0	0

Total Amount (a+b+c)	155.30049031387
Total GST (a)	0
LABOUR CESS @ 1% (+)	1.5530049031387
Grand Total	156.85349521701
Say For Unit 1 (Grand Total/1)	156.85349521701

Raisen Murmu
JE
Soro Block

Nirmala Kanta Parida
AEE
Soro Block

Satyanath Naik
BDO
Soro Block