

Analysis

**OD/363/3473/275096/429160/00064590 : REPAIR AND MAINTENANCE OF AWC
DUDUMPADAR
Block : Kundura, Gram Panchayat : P Hulabhata
Created By:P Manasmita**

Item 1

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	538.44	19.276152	3.46970736
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	75.86	1.1379	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	36.677	1.3130366	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	536.41	8.04615	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	519.8	7.797	0

Total Amount (a+b+c)

171.6902386

Total GST (a)

3.46970736

LABOUR CESS @ 1% (+)

1.7515994596

Grand Total

176.9115454196

Say For Unit 1 (Grand Total/1)

176.9115454196

Item 2

Painting (AR0918ca): Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work
Finishing wall two coats with weather coat with one coat oilbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901ci)					
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	125.43	10.53612	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.36677	0.04584625	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0.36677	0.03080868	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0	0	0

Total Amount (a+b+c)	155.31946041387
Total GST (a)	0
LABOUR CESS @ 1% (+)	1.5531946041387
Grand Total	156.87265501801
Say For Unit 1 (Grand Total/1)	156.87265501801

Item 3

Dismantling (AR1612): Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.

Sub-Item of Work
Dismantling and removing 2.5 cm. thick artificial stone flooring

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.25	Per day	462	577.5	0
LR001 : Male mulia	0.75	Per day	462	346.5	0

Total Amount (a+b+c)	924
Total GST (a)	0
LABOUR CESS @ 1% (+)	9.24
Grand Total	933.24
Say For Unit 1 (Grand Total/9.3)	100.34838709677

Item 4

Dismantling (AR1613): Removing old lime or cement plaster from walls including raking out joints 12 mm deep and removing the debris within 50m lead and as per direction of Engineer-in-Charge.

Sub-Item of Work
Removing old lime or cement plaster

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	1	Per day	462	462	0

Total Amount (a+b+c)	462
Total GST (a)	0
LABOUR CESS @ 1% (+)	4.62
Grand Total	466.62
Say For Unit 1 (Grand Total/9.3)	50.174193548387

NAYANA PATNAIK
JE
Kundura Block

RAMA KANTA NAYAK
AEE
Kundura Block

P Manasmita
BDO
Kundura Block