

Analysis

OD/362/3459/119590/407303/00065156 : IMPROVEMENT OF MUSLIM SAHI BACK SIDE ROAD

Block : Begunia, Gram Panchayat : Pangarasingh
Created By:Santosh kumar Jena

Item 1
Earth Work (AR0101a): Earth work in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.
Sub-Item of Work Earthwork in ordinary soil within 50m, initial lead and 1.5m, initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	16	Per day	462	7392	0
LR001 : Male mulia	16	Per day	462	7392	0
Total Amount (a+b+c)				14784	
Total GST (a)					0
LABOUR CESS @ 1% (+)					147.84
Grand Total					14931.84
Say For Unit 1 (Grand Total/100)					149.3184

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.19	5619	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	953.91	95391	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM029 : Sand for filling and road blinding	100	1 Cum	43.25	4325	0
---	-----	-------	-------	------	---

Total Amount (a+b+c)	111045.32
Total GST (a)	0
LABOUR CESS @ 1% (+)	1110.4532
Grand Total	112155.7732
Say For Unit 1 (Grand Total/100)	1121.557732

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	544.6	1247.134	224.48412
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	62.58	30.0384	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	953.91	457.8768	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	471.31	452.4576	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	43.25	20.76	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	309.5	297.12	0

Total Amount (a+b+c)	5434.16308
Total GST (a)	224.48412
LABOUR CESS @ 1% (+)	56.586472
Grand Total	5715.233672

Say For Unit 1 (Grand Total/1)	5715.233672
---------------------------------------	-------------

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	544.6	1759.058	316.63044
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	62.58	28.161	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1372.71	1235.439	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	953.91	429.2595	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	471.31	424.179	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	43.25	19.4625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	309.5	278.55	0

Total Amount (a+b+c)	6780.73336
-----------------------------	------------

Total GST (a)	316.63044
LABOUR CESS @ 1% (+)	70.973638
Grand Total	7168.337438
Say For Unit 1 (Grand Total/1)	7168.337438

ADITYA NARAYAN SINGH
JE
Begunia Block

SUSMITA MISHRA
AEE
Begunia Block

Santosh kumar Jena
BDO
Begunia Block