

## Analysis

**OD/354/3385/275061/410907/00065262 : Repair and maintenance of UPS Gunduribadi  
Block : Surada, Gram Panchayat : Bhagabanpur  
Created By:TANAMAYA PATRA**

<b>Item 1</b>
<b>Concrete (AR0307):</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.
Sub-Item of Work <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	3.2	Per day	462	1478.4	0
<b>LR025</b> : Mason	0.68	Per day	562	382.16	0
<b>BRM340</b> : Cement	3.23	1 Qntl.	568.23	1835.3829	330.368922
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	66.23	29.8035	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	24.787	80.06201	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	406.21	365.589	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	205.25	92.3625	0

<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	290.5	261.45	0
<b>Total Amount (a+b+c)</b>	6582.46741				
<b>Total GST (a)</b>	330.368922				
<b>LABOUR CESS @ 1% (+)</b>	69.12836332				
<b>Grand Total</b>	6981.96469532				
<b>Say For Unit 1 (Grand Total/1)</b>	6981.96469532				

## Item 2

**Other Building Items. (AR1901B):** Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work  
**Fifth Floor**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM174</b> : White Cement.	0.076	1Qntl	2017.18	153.30568	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	568.23	610.27902	109.8502236
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	66.23	13.9083	0
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sq.m.	651.08	6510.8	0
<b>LR001</b> : Male mulia	2.756768175	Per day	462	1273.62689685	0
<b>LR044</b> : Mason	2.756768175	Per day	612	1687.1421231	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM174</b> : White Cement.	0.076	1Qntl	24.787	1.883812	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	24.787	26.621238	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	341.11	71.6331	0
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sq.m.	9.6011111	96.011111	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM174</b> : White Cement.	0.076	1Qntl	0	0	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	205.25	43.1025	0
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

<b>Total Amount (a+b+c)</b>	10488.31378095
<b>Total GST (a)</b>	109.8502236
<b>LABOUR CESS @ 1% (+)</b>	105.9816400455
<b>Grand Total</b>	10704.145644596
<b>Say For Unit 1 (Grand Total/10)</b>	1070.4145644596

### Item 3

**Flooring (AR0817aa):** Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

**Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
<b>BRMMR0027</b> : Wax Polish	10	1 Sqm	8.5	85	0
<b>LR044</b> : Mason	3.25	Per day	612	1989	0
<b>LR001</b> : Male mulia	3.25	Per day	462	1501.5	0
<b>LR008</b> : Sangi mulia	7.6	Per day	512	3891.2	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	568.23	781.31625	140.636925
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	66.23	9.9345	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	9.6011111	96.011111	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	24.787	34.082125	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	341.11	51.1665	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	205.25	30.7875	0

<b>Total Amount (a+b+c)</b>	14980.797986
<b>Total GST (a)</b>	140.636925
<b>LABOUR CESS @ 1% (+)</b>	151.21434911
<b>Grand Total</b>	15272.64926011
<b>Say For Unit 1 (Grand Total/10)</b>	1527.264926011

<b>Item 4</b>
<b>Painting (AR0903b):</b> Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.
Sub-Item of Work <b>Painting two coats of enamel paint with a coat of red oxide primer over iron surface</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: Painting (AR0901b)</b>					
<b>LR048</b> : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
<b>BRM137</b> : Red oxide Primer	0.054	1 Litre	142.7	7.7058	0
<b>LR001</b> : Male mulia	0.053763440860215	Per day	462	24.838709677419	0
<b>Combine :: Painting (AR0903)</b>					
<b>LR048</b> : Painter/ Polisher	0.13440860215054	Per day	612	82.258064516129	0
<b>LR001</b> : Male mulia	0.11827956989247	Per day	462	54.645161290323	0
<b>BRM141</b> : Enamel paint	0.125	1 Litre	205.34	25.6675	0

<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST

<b>BRM137</b> : Red oxide Primer	0.054	1 Litre	0.24787	0.01338498	0
<b>BRM141</b> : Enamel paint	0.125	1 Litre	0.24787	0.03098375	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM137</b> : Red oxide Primer	0.054	1 Litre	0	0	0
<b>BRM141</b> : Enamel paint	0.125	1 Litre	0	0	0

<b>Total Amount (a+b+c)</b>	228.06283002032
<b>Total GST (a)</b>	0
<b>LABOUR CESS @ 1% (+)</b>	2.2806283002032
<b>Grand Total</b>	230.34345832053
<b>Say For Unit 1 (Grand Total/1)</b>	230.34345832053

**Item 5**

**Painting (AR0918cb):** Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

**Finishing wall two coats with weather coat with one coat waterbound Primer**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: Painting (AR0918f)</b>					
<b>BRM255</b> : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
<b>LR001</b> : Male mulia	0.064	Per day	462	29.568	0
<b>LR048</b> : Painter/ Polisher	0.054	Per day	612	33.048	0
<b>Combine :: Painting (AR0901di)</b>					
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
<b>LR048</b> : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
<b>LR001</b> : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255</b> : Weather Coat (I.S.I.)	0.125	1 Ltr	0.24787	0.03098375	0
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.24787	0.022388258064516	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255</b> : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

<b>Total Amount (a+b+c)</b>	159.12405749194
<b>Total GST (a)</b>	0
<b>LABOUR CESS @ 1% (+)</b>	1.5912405749194
<b>Grand Total</b>	160.71529806685
<b>Say For Unit 1 (Grand Total/1)</b>	160.71529806685

**Kanheaya kar  
JE  
Surada Block**

**A SANTOSH KUMAR PATRO  
AEE  
Surada Block**

**TANAMAYA PATRA  
BDO  
Surada Block**