

Analysis

OD/365/3506/120339/389102/00063179 : Const. of C.C. road from main road to Goura Singh house at Rangamatia
Block : Samakhunta, Gram Panchayat : Rangamatia
Created By:MUNA SETHI

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
LABOUR CESS @ 1% (+)					238.392
Grand Total					24077.592
Say For Unit 1 (Grand Total/100)					240.77592

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	60.43	6043	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM029 : Sand for filling and road blinding	100	1 Cum	575.25	57525	0
---------------------------------------------	-----	-------	--------	-------	---

Total Amount (a+b+c)	103389.32
Total GST (a)	0
LABOUR CESS @ 1% (+)	1033.8932
Grand Total	104423.2132
Say For Unit 1 (Grand Total/100)	1044.232132

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	608	1392.32	250.6176
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	66.85	32.088	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	705.67	677.4432	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	575.25	276.12	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	551.5	529.44	0

Total Amount (a+b+c)	5999.92028
Total GST (a)	250.6176
LABOUR CESS @ 1% (+)	62.5053788
Grand Total	6313.0432588

Say For Unit 1 (Grand Total/1)	6313.0432588
--------------------------------	--------------

Item 4

Concrete (AR0307a): Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	1085.19	976.671	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	608	1963.84	353.4912
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	66.85	30.0825	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	705.67	635.103	0
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	551.5	496.35	0
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	575.25	258.8625	0

Total Amount (a+b+c)	7121.03286
Total GST (a)	353.4912

LABOUR CESS @ 1% (+)	74.7452406
Grand Total	7549.2693006
Say For Unit 1 (Grand Total/1)	7549.2693006

Item 5

R.C.C. Work (AR0410f): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor in ground floor R.C.C. walls and fins including attached pilasters

Sub-Item of Work

Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	10.08	1Mtr.	41.81	421.4448	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.1223	1Cum.	58374.79	7139.236817	0
LR010 : Mate	13.5	Per day	512	6912	0
LR027 : Carpenter	13.5	Per day	562	7587	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.1238	1Mtr.	245.856	30.4369728	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.1223	1Cum.	245.856	30.0681888	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.1238	1Mtr.	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.1223	1Cum.	0	0	0

Total Amount (a+b+c)	22120.1867786
Total GST (a)	0
LABOUR CESS @ 1% (+)	221.201867786
Grand Total	22341.388646386
Say For Unit 1 (Grand Total/23.9)	934.78613583205

Item 6

R.C.C. Work (AR0410a): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height

Sub-Item of Work
Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	5.6	1Mtr	51.87	290.472	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	58374.79	2638.540508	0
LR008 : Sangi mulia	2.75	Per day	512	1408	0
LR027 : Carpenter	2.75	Per day	562	1545.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.069	1Mtr	245.856	16.964064	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	245.856	11.1126912	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.069	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	0	0	0

Total Amount (a+b+c)	5910.5892632				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	59.105892632				
Grand Total	5969.695155832				
Say For Unit 1 (Grand Total/9)	663.29946175911				

Item 7

R.C.C. Work (AR0404B): R.C.C. work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge(Nominal mix as per IS-456, Table-9).

Sub-Item of Work
Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips.(Nominal mix as per IS-456, Table-9).

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1380	496.8	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	608	2111.7664	380.117952
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	66.85	30.0825	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	705.67	254.0412	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	705.67	381.0618	0
BRM340 : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	551.5	198.54	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	551.5	297.81	0
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	575.25	258.8625	0

Total Amount (a+b+c)	6108.9841556
Total GST (a)	380.117952
LABOUR CESS @ 1% (+)	64.891021076
Grand Total	6553.993128676

Say For Unit 1 (Grand Total/1)	6553.993128676
--------------------------------	----------------

Item 8
R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.
Sub-Item of Work Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90	720	0
BRM341 : Steel	10.5	1 Qntl.	6176.71	64855.455	11673.9819

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	30.732	322.686	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	71655.421
Total GST (a)	11673.9819
LABOUR CESS @ 1% (+)	833.294029
Grand Total	84162.696929
Say For Unit 1 (Grand Total/10)	8416.2696929

SUSHANTA PANDUA
JE
Samakhunta Block

SUVENDU NAIK
AEE
Samakhunta Block

MUNA SETHI
BDO
Samakhunta Block