

Analysis

**OD/362/3460/119598/407473/00017946 : Repair & Maintenance of Govt PS Godibari
Block : Bhubaneswar, Gram Panchayat : Andhrua
Created By:Deviprasad Mohanty**

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.19	5619	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details					
-------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	43.25	4325	0
Total Amount (a+b+c)				49765.32	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)				3732.399	
CONTRACTOR PROFIT @ 7.5% (+)				4012.328925	
LABOUR CESS @ 1% (+)				575.10047925	
Grand Total				58085.14840425	
Say For Unit 1 (Grand Total/100)				580.8514840425	

Item 3

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	544.6	19.49668	3.5094024
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	62.58	0.9387	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	24.787	0.8873746	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	341.11	5.11665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	43.25	0.64875	0

Total Amount (a+b+c)				161.2081546	
Total GST (a)					3.5094024
OVERHEAD CHARGES @ 7.5% (+)				12.353816775	
CONTRACTOR PROFIT @ 7.5% (+)				13.280353033125	

LABOUR CESS @ 1% (+)	1.9035172680813
Grand Total	192.25524407621
Say For Unit 1 (Grand Total/1)	192.25524407621

Item 4

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	544.6	365.9712	65.874816
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	62.58	17.5224	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	341.11	95.5108	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	1.01135	353.9725	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	43.25	12.11	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	0	0	0

Total Amount (a+b+c)	4866.456264
Total GST (a)	65.874816
OVERHEAD CHARGES @ 7.5% (+)	369.924831
CONTRACTOR PROFIT @ 7.5% (+)	397.669193325
LABOUR CESS @ 1% (+)	56.99925104325
Grand Total	5756.9243553682
Say For Unit 1 (Grand Total/1)	5756.9243553682

Item 5

Masonry Stone Work (AR0717): Laterite stone masonry in cement mortar (1:6) in foundation and plinth cost conveyance, royalty, taxes of all materials, labor, required for the work, etc. complete and as per direction of the Engineer-in-charge.

Sub-Item of Work
Laterite stone masonry

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	544.6	311.5112	56.072016
LR001 : Male mulia	1.21	Per day	462	559.02	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.175	Per day	612	107.1	0
LR008 : Sangi mulia	1.41	Per day	512	721.92	0
LR052 : Stone dresser/ Cutter	2.12	Per day	612	1297.44	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	62.58	15.0192	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	729.98	729.98	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	24.787	14.178164	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	341.11	81.8664	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	796.81	796.81	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.572	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.24	1 Cum	43.25	10.38	0
BRM079 : Laterite Stone rough dressed	1	1 Cum.	309.5	309.5	0

Total Amount (a+b+c)	5544.824964
Total GST (a)	56.072016

OVERHEAD CHARGES @ 7.5% (+)	420.0672735
CONTRACTOR PROFIT @ 7.5% (+)	451.5723190125
LABOUR CESS @ 1% (+)	64.725365725125
Grand Total	6537.2619382376
Say For Unit 1 (Grand Total/1)	6537.2619382376

**Itishree P Behura
JE
Bhubaneswar Block**

**Sri Niranjana Biswal
AEE
Bhubaneswar Block**

**Deviprasad Mohanty
BDO
Bhubaneswar Block**