

Analysis

**OD/369/3545/121063/409773/00070164 : Construction of Basantei Bhoga Mandap,
Chasapada, Bijayramchandrapur GP
Block : Sadar, Gram Panchayat : Bijayramchandrapur
Created By:SAMBEET SATAPATHY**

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	60.5	6050	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0
b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	627.55	62755	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	75.25	7525	0

Total Amount (a+b+c)	82040.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	6153.024				
CONTRACTOR PROFIT @ 7.5% (+)	6614.5008				
LABOUR CESS @ 1% (+)	948.078448				
Grand Total	95755.923248				
Say For Unit 1 (Grand Total/100)	957.55923248				

Item 3
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	570.62	1306.7198	235.209564
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	75	36	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	985	945.6	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	45	103.05	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	861.91	413.7168	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	1073.51	1030.5696	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	75.25	36.12	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	170.5	163.68	0

Total Amount (a+b+c)	5938.4162
Total GST (a)	235.209564
OVERHEAD CHARGES @ 7.5% (+)	463.0219323
CONTRACTOR PROFIT @ 7.5% (+)	497.7485772225
LABOUR CESS @ 1% (+)	71.343962735225
Grand Total	7205.7402362577
Say For Unit 1 (Grand Total/1)	7205.7402362577

Item 4

Masonry Brick Work (AR0603c): Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	4.55488	1821.952	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	570.62	383.45664	69.0221952
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	75	21	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	1.351072	540.4288	0
BRM340 : Cement	0.672	1 Qntl.	45	30.24	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	861.91	241.3348	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	0	0	0

BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	75.25	21.07	0
Total Amount (a+b+c)	5231.30224				
Total GST (a)	69.0221952				
OVERHEAD CHARGES @ 7.5% (+)	397.52433264				
CONTRACTOR PROFIT @ 7.5% (+)	427.338657588				
LABOUR CESS @ 1% (+)	61.25187425428				
Grand Total	6186.4392996823				
Say For Unit 1 (Grand Total/1)	6186.4392996823				

Item 5

Masonry Brick Work (AR0603ci): Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	4.55488	1821.952	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	570.62	383.45664	69.0221952
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	75	21	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	1.351072	540.4288	0
BRM340 : Cement	0.672	1 Qntl.	45	30.24	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	861.91	241.3348	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	400	1000 Nos	0	0	0
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	75.25	21.07	0

Total Amount (a+b+c)	5264.30224
Total GST (a)	69.0221952
OVERHEAD CHARGES @ 7.5% (+)	399.99933264
CONTRACTOR PROFIT @ 7.5% (+)	429.999282588
LABOUR CESS @ 1% (+)	61.63323050428
Grand Total	6224.9562809323
Say For Unit 1 (Grand Total/1)	6224.9562809323

Item 6

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	5809.9	61003.95	10980.711

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	45	472.5	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	67954.53
Total GST (a)	10980.711

OVERHEAD CHARGES @ 7.5% (+)	5920.143075
CONTRACTOR PROFIT @ 7.5% (+)	6364.153805625
LABOUR CESS @ 1% (+)	912.19537880625
Grand Total	92131.733259431
Say For Unit 1 (Grand Total/10)	9213.1733259431

Item 7

R.C.C. Work (AR0404A): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	570.62	1981.934446	356.74820028
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	75	33.75	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	45	156.2985	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	861.91	387.8595	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1073.51	386.4636	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1073.51	579.6954	0
--	------	-----------	---------	----------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	75.25	33.8625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	170.5	61.38	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	170.5	92.07	0

Total Amount (a+b+c)	6043.813946
Total GST (a)	356.74820028
OVERHEAD CHARGES @ 7.5% (+)	480.042160971
CONTRACTOR PROFIT @ 7.5% (+)	516.04532304383
LABOUR CESS @ 1% (+)	73.966496302948
Grand Total	7470.6161265978
Say For Unit 1 (Grand Total/1)	7470.6161265978

Item 8

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.570465023
CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972
LABOUR CESS @ 1% (+)	24.741232485627
Grand Total	2498.8644810484
Say For Unit 1 (Grand Total/10)	249.88644810484

Item 9
R.C.C. Work (AR0410d): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm
Sub-Item of Work Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	2.32	1Mtr	51.87	120.3384	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	58374.79	1272.570422	0
LR008 : Sangi mulia	2.75	Per day	512	1408	0
LR027 : Carpenter	2.75	Per day	562	1545.5	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0238	1Mtr	198.296	4.7194448	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	198.296	4.3228528	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0238	1Mtr	0	0	0

BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	0	0	0
--	--------	-------	---	---	---

Total Amount (a+b+c)	4355.4511196
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	326.65883397
CONTRACTOR PROFIT @ 7.5% (+)	351.15824651775
LABOUR CESS @ 1% (+)	50.332682000878
Grand Total	5083.6008820886
Say For Unit 1 (Grand Total/4.2)	1210.3811624021

Item 10

R.C.C. Work (AR0410a): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height

Sub-Item of Work

Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	5.6	1Mtr	51.87	290.472	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	58374.79	2638.540508	0
LR008 : Sangi mulia	2.75	Per day	512	1408	0
LR027 : Carpenter	2.75	Per day	562	1545.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.069	1Mtr	198.296	13.682424	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	198.296	8.9629792	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.069	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	0	0	0

Total Amount (a+b+c)	5905.1579112
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	442.88684334
CONTRACTOR PROFIT @ 7.5% (+)	476.1033565905
LABOUR CESS @ 1% (+)	68.241481111305

Grand Total	6892.3895922418
Say For Unit 1 (Grand Total/9)	765.82106580465

Item 11

Plastering (AR1017): 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
20mm thick cement Plaster in CM (1:4) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.0744	1 Qntl.	570.62	42.454128	7.64174304
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	75	1.575	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0744	1 Qntl.	45	3.348	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	861.91	18.10011	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0744	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	75.25	1.58025	0

Total Amount (a+b+c)	267.857488
Total GST (a)	7.64174304
OVERHEAD CHARGES @ 7.5% (+)	20.662442328
CONTRACTOR PROFIT @ 7.5% (+)	22.2121255026
LABOUR CESS @ 1% (+)	3.183737988706
Grand Total	321.55753685931
Say For Unit 1 (Grand Total/1)	321.55753685931

Item 12

Plastering (AR1027): 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.

Sub-Item of Work
6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.12	Per day	462	55.44	0
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0372	1 Qntl.	570.62	21.227064	3.82087152
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	75	0.5625	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	45	1.674	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	861.91	6.464325	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	75.25	0.564375	0

Total Amount (a+b+c)	187.712264
Total GST (a)	3.82087152
OVERHEAD CHARGES @ 7.5% (+)	14.364985164
CONTRACTOR PROFIT @ 7.5% (+)	15.4423590513
LABOUR CESS @ 1% (+)	2.213404797353
Grand Total	223.55388453265
Say For Unit 1 (Grand Total/1)	223.55388453265

Item 13

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0

BRM340 : Cement	0.0358	1 Qntl.	570.62	20.428196	3.67707528
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	75	1.125	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	45	1.611	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	861.91	12.92865	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	75.25	1.12875	0

Total Amount (a+b+c)	171.341596
Total GST (a)	3.67707528
OVERHEAD CHARGES @ 7.5% (+)	13.126400346
CONTRACTOR PROFIT @ 7.5% (+)	14.11088037195
LABOUR CESS @ 1% (+)	2.0225595199795
Grand Total	204.27851151793
Say For Unit 1 (Grand Total/1)	204.27851151793

Item 14

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	570.62	24.53666	4.4165988
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	75	1.35	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	45	1.935	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	861.91	15.51438	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	75.25	1.3545	0

Total Amount (a+b+c)	245.49054
Total GST (a)	4.4165988
OVERHEAD CHARGES @ 7.5% (+)	18.74303541
CONTRACTOR PROFIT @ 7.5% (+)	20.14876306575
LABOUR CESS @ 1% (+)	2.8879893727575
Grand Total	291.68692664851
Say For Unit 1 (Grand Total/1)	291.68692664851

Item 15

Flooring (AR0809): 10cm thick dry K.B. brick khoa well watered & rammed to receive A.S.flooring incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.

Sub-Item of Work

10cm thick dry K.B. brick khoa well watered & rammed to receive A.S.flooring incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.22	Per day	462	101.64	0
LR001 : Male mulia	0.16	Per day	462	73.92	0
LR025 : Mason	0.05	Per day	562	28.1	0
BRM020 : K.B. bricks Khoa 4 Cm.size	0.14	1 Cum	380	53.2	0

Total Amount (a+b+c)	256.86
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	19.2645
CONTRACTOR PROFIT @ 7.5% (+)	20.7093375
LABOUR CESS @ 1% (+)	2.968338375
Grand Total	299.802175875
Say For Unit 1 (Grand Total/1)	299.802175875

Item 16

Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work
Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2017.18	153.30568	0
BRM340 : Cement	1.074	1 Qntl.	570.62	612.84588	110.3122584
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	75	15.75	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	45	3.42	0
BRM340 : Cement	1.074	1 Qntl.	45	48.33	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	861.91	181.0011	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	15.1648337	151.648337	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	75.25	15.8025	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)

10012.743497

Total GST (a)

110.3122584

OVERHEAD CHARGES @ 7.5% (+)

759.229181655

CONTRACTOR PROFIT @ 7.5% (+)

816.17137027912

LABOUR CESS @ 1% (+)

116.98456307334

Grand Total

11815.440870407

Say For Unit 1 (Grand Total/10)	1181.5440870407
---------------------------------	-----------------

Item 17

Flooring (AR0817ad): Fixing Vitrified Tile 600mm x 1200mm size of approved shade and make (Single Charge) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work
Fixing Vitrified Tile 600mm x 1200mm size of approved shade and make (Single Charge) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMM332 : Vitrified Floor Tile 600mm x 1200mm size of approved shade and make (Single Charge) (New miscellaneous Materials)	10	1 Sqm.	611.26	6112.6	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	570.62	784.6025	141.22845
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	75	11.25	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	1.375	1 Qntl.	45	61.875	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	861.91	129.2865	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	75.25	11.2875	0

Total Amount (a+b+c)	14577.6015
Total GST (a)	141.22845
OVERHEAD CHARGES @ 7.5% (+)	1103.91224625
CONTRACTOR PROFIT @ 7.5% (+)	1186.7056647188
LABOUR CESS @ 1% (+)	170.09447860969
Grand Total	17179.542339578
Say For Unit 1 (Grand Total/10)	1717.9542339578

Item 18

Painting (AR0918cb): Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Finishing wall two coats with weather coat with one coat waterbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901di)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.45	0.05625	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.45	0.040645161290323	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

Total Amount (a+b+c)	159.16758064516
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11.937568548387
CONTRACTOR PROFIT @ 7.5% (+)	12.832886189516
LABOUR CESS @ 1% (+)	1.8393803538306
Grand Total	185.7774157369
Say For Unit 1 (Grand Total/1)	185.7774157369

Subrat Mangaraj
JE
Sadar Block

Ashok Kumar Dalabehera
AEE
Sadar Block

SAMBEET SATAPATHY
BDO
Sadar Block