

## Analysis

**OD/346/3309/116330/393696/00069786 : Repair & Maintenance of Nuagan AWC**

**Block : Soro, Gram Panchayat : Singakhunta**

**Created By: Satyanath Naik**

<b>Item 1</b>
<b>Earth Work (AR0102aa):</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work <b>Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
<b>Total Amount (a+b+c)</b>				23839.2	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>					1787.94
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>					1922.0355
<b>LABOUR CESS @ 1% (+)</b>					275.491755
<b>Grand Total</b>					27824.667255
<b>Say For Unit 1 (Grand Total/100)</b>					278.24667255

<b>Item 2</b>
<b>Earth Work (AR0115):</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Filling foundation and plinth with sand well watered and rammed</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	953.91	95391	0

c) Royalty Rate Details					
-------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM029</b> : Sand for filling and road blinding	100	1 Cum	442.25	44225	0
<b>Total Amount (a+b+c)</b>				152520.32	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>				11439.024	
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>				12296.9508	
<b>LABOUR CESS @ 1% (+)</b>				1762.562948	
<b>Grand Total</b>				178018.857748	
<b>Say For Unit 1 (Grand Total/100)</b>				1780.18857748	

### Item 3

**Concrete (AR0303):** Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work  
**Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR025</b> : Mason	0.18	Per day	562	101.16	0
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	2.5	Per day	462	1155	0
<b>BRM340</b> : Cement	2.29	1 Qntl.	537.2	1230.188	221.43384
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	2.29	1 Qntl.	24.787	56.76223	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	953.91	457.8768	0
<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	341.11	327.4656	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	2.29	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	552.5	530.4	0

<b>Total Amount (a+b+c)</b>	5710.27503
-----------------------------	------------

<b>Total GST (a)</b>	221.43384
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	444.87816525
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	478.24402764375
<b>LABOUR CESS @ 1% (+)</b>	68.548310628938
<b>Grand Total</b>	6923.3793735227
<b>Say For Unit 1 (Grand Total/1)</b>	6923.3793735227

#### Item 4

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	3.2	Per day	462	1478.4	0
<b>LR025</b> : Mason	0.68	Per day	562	382.16	0
<b>BRM340</b> : Cement	3.23	1 Qntl.	537.2	1735.156	312.32808
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	24.787	80.06201	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	953.91	429.2595	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	341.11	306.999	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	0	0	0

<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	552.5	497.25	0

<b>Total Amount (a+b+c)</b>	7046.65301
<b>Total GST (a)</b>	312.32808
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	551.92358175
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	593.31785038125
<b>LABOUR CESS @ 1% (+)</b>	85.042225221312
<b>Grand Total</b>	8589.2647473526
<b>Say For Unit 1 (Grand Total/1)</b>	8589.2647473526

<b>Item 5</b>
<b>R.C.C. Work (AR0404Aa):</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)
Sub-Item of Work <b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips</b>

<b>a) Specific Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	537.2	1865.85676	335.8542168
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0

Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	953.91	429.2595	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	552.5	198.9	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	552.5	298.35	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	6070.707377146
Total GST (a)	335.8542168
OVERHEAD CHARGES @ 7.5% (+)	480.49211954595
CONTRACTOR PROFIT @ 7.5% (+)	516.5290285119
LABOUR CESS @ 1% (+)	74.035827420038
Grand Total	7477.6185694239
Say For Unit 1 (Grand Total/1)	7477.6185694239

**Item 6**

**R.C.C. Work (AR0404Ag):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	537.2	1865.85676	335.8542168
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
<b>Combine :: R.C.C. Work (AR0410a)</b>					
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	1Mtr	51.87	322.714392	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	58374.79	2931.418504388	0
<b>LR008</b> : Sangi mulia	3.05525	Per day	512	1564.288	0
<b>LR027</b> : Carpenter	3.05525	Per day	562	1717.0505	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	953.91	429.2595	0

<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	198.296	15.201173064	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	198.296	9.9578698912	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	552.5	198.9	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	552.5	298.35	0
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	0	0	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	0	0	0

<b>Total Amount (a+b+c)</b>	12310.196886443
<b>Total GST (a)</b>	335.8542168
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	948.45383274324
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1019.587870199
<b>LABOUR CESS @ 1% (+)</b>	146.14092806185
<b>Grand Total</b>	14760.233734247
<b>Say For Unit 1 (Grand Total/1)</b>	14760.233734247

**Item 7**

**Masonry Brick Work (AR0603bi):** Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance  $\pm 8$  percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	0.14	Per day	462	64.68	0
<b>BRMMR0025</b> : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0

<b>LR001</b> : Male mulia	2.82	Per day	462	1302.84	0
<b>LR025</b> : Mason	1.05	Per day	562	590.1	0
<b>LR044</b> : Mason	0.35	Per day	612	214.2	0
<b>BRM340</b> : Cement	0.672	1 Qntl.	537.2	360.9984	64.979712
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.672	1 Qntl.	24.787	16.656864	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	953.91	267.0948	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.30585	457.0475	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.672	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	442.25	123.83	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

<b>Total Amount (a+b+c)</b>	5251.866464
<b>Total GST (a)</b>	64.979712
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	398.7634632
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	428.67072294
<b>LABOUR CESS @ 1% (+)</b>	61.4428036214
<b>Grand Total</b>	6205.7231657614
<b>Say For Unit 1 (Grand Total/1)</b>	6205.7231657614

#### Item 8

**R.C.C. Work (AR0409):** Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

**Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90	720	0
BRM341 : Steel	10.5	1 Qntl.	6186.01	64953.105	11691.5589

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	24.787	260.2635	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

<b>Total Amount (a+b+c)</b>					71690.6485
<b>Total GST (a)</b>					11691.5589
<b>OVERHEAD CHARGES @ 7.5% (+)</b>					6253.665555
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>					6722.690471625
<b>LABOUR CESS @ 1% (+)</b>					963.58563426625
<b>Grand Total</b>					97322.149060891
<b>Say For Unit 1 (Grand Total/10)</b>					9732.2149060891

**Item 9**

**Plastering (AR1014):** 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

**16mm thick cement Plaster in CM (1:6) over brick work in inside.**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	537.2	23.0996	4.157928
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM340</b> : Cement	0.043	1 Qntl.	24.787	1.065841	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	1 Cum	953.91	17.17038	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.043	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	1 Cum	442.25	7.9605	0

<b>Total Amount (a+b+c)</b>	251.480161
<b>Total GST (a)</b>	4.157928
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	19.172856675
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	20.610820925625
<b>LABOUR CESS @ 1% (+)</b>	2.9542176660063
<b>Grand Total</b>	298.37598426663
<b>Say For Unit 1 (Grand Total/1)</b>	298.37598426663

**Item 10**

**Plastering (AR1004):** 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

**12mm thick cement plaster (1:6) over Brick work in inside**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	0.05	Per day	462	23.1	0
<b>LR001</b> : Male mulia	0.07	Per day	462	32.34	0
<b>LR025</b> : Mason	0.14	Per day	562	78.68	0
<b>BRM340</b> : Cement	0.0358	1 Qntl.	537.2	19.23176	3.4617168
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.0358	1 Qntl.	24.787	0.8873746	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	1 Cum	953.91	14.30865	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.0358	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	1 Cum	442.25	6.63375	0

<b>Total Amount (a+b+c)</b>	176.3347346
<b>Total GST (a)</b>	3.4617168
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	13.484733855
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	14.496088894125
<b>LABOUR CESS @ 1% (+)</b>	2.0777727414913
<b>Grand Total</b>	209.85504689062
<b>Say For Unit 1 (Grand Total/1)</b>	209.85504689062

### Item 11

**Other Building Items. (AR1901B):** Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work

**Vitrified Tile 600mmx600mm Plain Ivory**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM174</b> : White Cement.	0.076	1Qntl	2017.18	153.30568	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	537.2	576.9528	103.851504
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	76.88	16.1448	0
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
<b>LR001</b> : Male mulia	2.16	Per day	462	997.92	0
<b>LR044</b> : Mason	2.16	Per day	612	1321.92	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM174</b> : White Cement.	0.076	1Qntl	24.787	1.883812	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	24.787	26.621238	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	953.91	200.3211	0
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	12.8738891	128.738891	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM174</b> : White Cement.	0.076	1Qntl	0	0	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	442.25	92.8725	0
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

<b>Total Amount (a+b+c)</b>	10027.480821
<b>Total GST (a)</b>	103.851504
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	759.849924375
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	816.83866870312
<b>LABOUR CESS @ 1% (+)</b>	117.08020918078
<b>Grand Total</b>	11825.101127259
<b>Say For Unit 1 (Grand Total/10)</b>	1182.5101127259

## Item 12

**Flooring (AR0817aa):** Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

**Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
<b>BRMMR0027</b> : Wax Polish	10	1 Sqm	8.5	85	0
<b>LR044</b> : Mason	3.25	Per day	612	1989	0
<b>LR001</b> : Male mulia	3.25	Per day	462	1501.5	0
<b>LR008</b> : Sangi mulia	7.6	Per day	512	3891.2	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	537.2	738.65	132.957
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	12.8738891	128.738891	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	24.787	34.082125	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	953.91	143.0865	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	442.25	66.3375	0

<b>Total Amount (a+b+c)</b>	15099.927016
<b>Total GST (a)</b>	132.957
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	1142.4663012
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1228.15127379
<b>LABOUR CESS @ 1% (+)</b>	176.0350159099
<b>Grand Total</b>	17779.5366069
<b>Say For Unit 1 (Grand Total/10)</b>	1777.95366069

### Item 13

**Painting (AR0901d):** Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

**Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
<b>LR048</b> : Painter/ Polisher	0.5	Per day	612	306	0
<b>LR001</b> : Male mulia	0.5	Per day	462	231	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.36677	0.286520724	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0
<b>Total Amount (a+b+c)</b>				661.520756724	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>				49.6140567543	
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>				53.335111010872	
<b>LABOUR CESS @ 1% (+)</b>				7.6446992448917	
<b>Grand Total</b>				772.11462373406	
<b>Say For Unit 1 (Grand Total/9.3)</b>				83.023077820867	

#### Item 14

**Painting (AR0920):** Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

**Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM140</b> : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
<b>LR048</b> : Painter/ Polisher	0.54	Per day	612	330.48	0
<b>LR001</b> : Male mulia	0.64	Per day	462	295.68	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM140</b> : Plastic Emulsion paint	1.25	1 Litre	0.36677	0.4584625	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM140</b> : Plastic Emulsion paint	1.25	1 Litre	0	0	0

<b>Total Amount (a+b+c)</b>				938.2934625	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>				70.3720096875	
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>				75.649910414063	
<b>LABOUR CESS @ 1% (+)</b>				10.843153826016	
<b>Grand Total</b>				1095.1585364276	
<b>Say For Unit 1 (Grand Total/10)</b>				109.51585364276	

**Item 15**

**Painting (AR0918hk):** Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).

Sub-Item of Work

**Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work(Outside)(For repair and maintenance).**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: Painting (AR0918fk)</b>					
<b>BRM255</b> : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
<b>LR001</b> : Male mulia	0.06528	Per day	462	30.15936	0
<b>LR048</b> : Painter/ Polisher	0.05508	Per day	612	33.70896	0
<b>Combine :: Painting (AR0901dik)</b>					
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
<b>LR048</b> : Painter/ Polisher	0.054838709677419	Per day	612	33.561290322581	0
<b>LR001</b> : Male mulia	0.054838709677419	Per day	462	25.335483870968	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255</b> : Weather Coat (I.S.I.)	0.125	1 Ltr	0.36677	0.04584625	0
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.36677	0.033127612903226	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255</b> : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

<b>Total Amount (a+b+c)</b>	161.55681805645
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	12.116761354234
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	13.025518455801
<b>LABOUR CESS @ 1% (+)</b>	1.8669909786649
<b>Grand Total</b>	188.56608884515
<b>Say For Unit 1 (Grand Total/1)</b>	188.56608884515

**Item 16**

**Painting (AR0901b):** Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work  
**Priming one coat in inner surface with primer of approved quality over iron work.**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
BRM137 : Red oxide Primer	0.5022	1 Litre	142.7	71.66394	0
LR001 : Male mulia	0.5	Per day	462	231	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.5022	1 Litre	0.36677	0.184191894	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.5022	1 Litre	0	0	0

<b>Total Amount (a+b+c)</b>	608.848131894
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	45.66360989205
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	49.088380633954
<b>LABOUR CESS @ 1% (+)</b>	7.0360012242
<b>Grand Total</b>	710.6361236442
<b>Say For Unit 1 (Grand Total/9.3)</b>	76.412486413355

**Item 17**

**Painting (AR0903i):** Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work  
**Painting two coats of enamel paint in outer surface paint (outer surface)**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	1.25	Per day	612	765	0
LR001 : Male mulia	1.1	Per day	462	508.2	0
BRM141 : Enamel paint	1.1625	1 Litre	205.34	238.70775	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0.36677	0.426370125	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0	0	0
<b>Total Amount (a+b+c)</b>				1512.334120125	
<b>Total GST (a)</b>				0	
<b>OVERHEAD CHARGES @ 7.5% (+)</b>				113.42505900938	
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>				121.93193843508	
<b>LABOUR CESS @ 1% (+)</b>				17.476911175695	
<b>Grand Total</b>				1765.1680287451	
<b>Say For Unit 1 (Grand Total/9.3)</b>				189.80301384356	

**Rojalin Jena**  
**JE**  
**Soro Block**

**Nirmala Kanta Parida**  
**AEE**  
**Soro Block**

**Satyanath Naik**  
**BDO**  
**Soro Block**