

## Analysis

### OD/361/3452/119466/385974/00015521 : IMPROVEMENT / COMPLETION OF KALYAN MANDAP AT PALASPANGA

Block : Kendujhar Sadar, Gram Panchayat : Palaspanga

Created By: Binod Chandra Panda

<b>Item 1</b>
<b>Earth Work (AR0102aa):</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work <b>Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
<b>Total Amount (a+b+c)</b>				23839.2	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>					1787.94
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>					1922.0355
<b>LABOUR CESS @ 1% (+)</b>					275.491755
<b>Grand Total</b>					27824.667255
<b>Say For Unit 1 (Grand Total/100)</b>					278.24667255

<b>Item 2</b>
<b>Earth Work (AR0115):</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Filling foundation and plinth with sand well watered and rammed</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	55	5500	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	898.71	89871	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	50.25	5025	0

Total Amount (a+b+c)	106106.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	7957.974				
CONTRACTOR PROFIT @ 7.5% (+)	8554.82205				
LABOUR CESS @ 1% (+)	1226.1911605				
Grand Total	123845.3072105				
Say For Unit 1 (Grand Total/100)	1238.453072105				

### Item 3

**Concrete (AR0303):** Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	567.52	1299.6208	233.931744
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	65	31.2	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	28.354	64.93066	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	898.71	431.3808	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	692.65	664.944	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	50.25	24.12	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	424.5	407.52	0

<b>Total Amount (a+b+c)</b>	5782.11626
<b>Total GST (a)</b>	233.931744
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	451.2036003
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	485.0438703225
<b>LABOUR CESS @ 1% (+)</b>	69.522954746225
<b>Grand Total</b>	7021.8184293687
<b>Say For Unit 1 (Grand Total/1)</b>	7021.8184293687

#### Item 4

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	3.2	Per day	462	1478.4	0
<b>LR025</b> : Mason	0.68	Per day	562	382.16	0
<b>BRM340</b> : Cement	3.23	1 Qntl.	567.52	1833.0896	329.956128
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	65	29.25	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1370	1233	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	28.354	91.58342	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	898.71	404.4195	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	692.65	623.385	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	0	0	0

<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	50.25	22.6125	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	424.5	382.05	0

<b>Total Amount (a+b+c)</b>	7126.75002
<b>Total GST (a)</b>	329.956128
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	559.2529611
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	601.1969331825
<b>LABOUR CESS @ 1% (+)</b>	86.171560422825
<b>Grand Total</b>	8703.3276027053
<b>Say For Unit 1 (Grand Total/1)</b>	8703.3276027053

### Item 5

**miscellaneous (ARM286):** Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.

Sub-Item of Work

**Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM029</b> : Sand for filling and road blinding	0.05	1 Cum	55	2.75	0
<b>BRMM286</b> : Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	1 Sqm	485.28	485.28	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM029</b> : Sand for filling and road blinding	0.05	1 Cum	898.71	44.9355	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM029</b> : Sand for filling and road blinding	0.05	1 Cum	50.25	2.5125	0

<b>Total Amount (a+b+c)</b>	535.478
<b>Total GST (a)</b>	0
<b>Grand Total</b>	8703.3276027053
<b>Say For Unit 1 (Grand Total/1)</b>	8703.3276027053

**Item 6**

**Masonry Brick Work (AR0603b):** Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance  $\pm 8$  percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	567.52	381.37344	68.6472192
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	65	18.2	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	1000 Nos	5.14255	1799.8925	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	28.354	19.053888	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	898.71	251.6388	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	1000 Nos	1.01135	353.9725	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	50.25	14.07	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	1000 Nos	0	0	0

<b>Total Amount (a+b+c)</b>	5010.021128
<b>Total GST (a)</b>	68.6472192
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	380.90012604
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	409.467635493
<b>LABOUR CESS @ 1% (+)</b>	58.69036108733

<b>Grand Total</b>	5927.7264698203
<b>Say For Unit 1 (Grand Total/1)</b>	5927.7264698203

### Item 7

**Masonry Brick Work (AR0603bi):** Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance  $\pm 8$  percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	567.52	381.37344	68.6472192
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	65	18.2	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2$ %	350	1000 Nos	5.14255	1799.8925	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	28.354	19.053888	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	898.71	251.6388	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2$ %	350	1000 Nos	1.01135	353.9725	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	50.25	14.07	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2$ %	350	1000 Nos	0	0	0

**Total Amount (a+b+c)**

5043.021128

<b>Total GST (a)</b>	68.6472192
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	383.37512604
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	412.128260493
<b>LABOUR CESS @ 1% (+)</b>	59.07171733733
<b>Grand Total</b>	5966.2434510703
<b>Say For Unit 1 (Grand Total/1)</b>	5966.2434510703

### Item 8

**Plastering (AR1014):** 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

**16mm thick cement Plaster in CM (1:6) over brick work in inside.**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	567.52	24.40336	4.3926048
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	65	1.17	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	28.354	1.219222	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	898.71	16.17678	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	50.25	0.9045	0

<b>Total Amount (a+b+c)</b>	244.673862
<b>Total GST (a)</b>	4.3926048
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	18.67998501
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	20.08098388575
<b>LABOUR CESS @ 1% (+)</b>	2.8782743569575
<b>Grand Total</b>	290.70571005271
<b>Say For Unit 1 (Grand Total/1)</b>	290.70571005271

**Item 9**

**Plastering (AR1004i):** 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

**12mm thick cement plaster (1:6) over Brick work in outside.**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	567.52	20.317216	3.65709888
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	65	0.975	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	28.354	1.0150732	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	898.71	13.48065	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	50.25	0.75375	0

**Total Amount (a+b+c)**

170.6616892

**Total GST (a)**

3.65709888

**OVERHEAD CHARGES @ 7.5% (+)**

13.073909106

**CONTRACTOR PROFIT @ 7.5% (+)**

14.05445228895

**LABOUR CESS @ 1% (+)**

2.0144714947495

**Grand Total**

203.4616209697

**Say For Unit 1 (Grand Total/1)**

203.4616209697

**Item 10**

**Masonry Brick Work (AR0603bi):** Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance  $\pm 8$  percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**First floor**

<b>a) Specific Rate Details</b>						
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>	
<b>LR002</b> : Female mulia	0.161	Per day	462	74.382	0	
<b>BRMMR0025</b> : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0	
<b>LR001</b> : Male mulia	3.243	Per day	462	1498.266	0	
<b>LR025</b> : Mason	1.2075	Per day	562	678.615	0	
<b>LR044</b> : Mason	0.4025	Per day	612	246.33	0	
<b>BRM340</b> : Cement	0.672	1 Qntl.	567.52	381.37344	68.6472192	
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	65	18.2	0	
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0	

<b>b) Carriage Rate Details</b>						
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>	
<b>BRM340</b> : Cement	0.672	1 Qntl.	28.354	19.053888	0	
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	898.71	251.6388	0	
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.01135	353.9725	0	

<b>c) Royalty Rate Details</b>						
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>	
<b>BRM340</b> : Cement	0.672	1 Qntl.	0	0	0	
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	50.25	14.07	0	
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0	

<b>Total Amount (a+b+c)</b>						5368.794128
<b>Total GST (a)</b>						68.6472192
<b>OVERHEAD CHARGES @ 7.5% (+)</b>						407.80810104
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>						438.393708618
<b>LABOUR CESS @ 1% (+)</b>						62.83643156858
<b>Grand Total</b>						6346.4795884266
<b>Say For Unit 1 (Grand Total/1)</b>						6346.4795884266

<b>Item 11</b>						
----------------	--	--	--	--	--	--

**Plastering (AR1014):** 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work  
**First Floor**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.1133	Per day	462	52.3446	0
LR001 : Male mulia	0.1339	Per day	462	61.8618	0
LR025 : Mason	0.1648	Per day	562	92.6176	0
BRM340 : Cement	0.043	1 Qntl.	567.52	24.40336	4.3926048
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	65	1.17	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	28.354	1.219222	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	898.71	16.17678	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	50.25	0.9045	0

<b>Total Amount (a+b+c)</b>	250.697862
<b>Total GST (a)</b>	4.3926048
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	19.13178501
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	20.56666888575
<b>LABOUR CESS @ 1% (+)</b>	2.9478892069575
<b>Grand Total</b>	297.73680990271
<b>Say For Unit 1 (Grand Total/1)</b>	297.73680990271

**Item 12**

**Painting (AR0918fk):** Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).

Sub-Item of Work

**Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)(For repair and maintenance) .**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM255</b> : Weather Coat (I.S.I.)	1.25	1 Ltr	194.79	243.4875	0
<b>LR001</b> : Male mulia	0.6528	Per day	462	301.5936	0
<b>LR048</b> : Painter/ Polisher	0.5508	Per day	612	337.0896	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255</b> : Weather Coat (I.S.I.)	1.25	1 Ltr	0.50945	0.6368125	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255</b> : Weather Coat (I.S.I.)	1.25	1 Ltr	0	0	0

<b>Total Amount (a+b+c)</b>	882.8075125				
<b>Total GST (a)</b>	0				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	66.2105634375				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	71.176355695313				
<b>LABOUR CESS @ 1% (+)</b>	10.201944316328				
<b>Grand Total</b>	1030.3963759491				
<b>Say For Unit 1 (Grand Total/10)</b>	103.03963759491				

**Ranjan Kumar Swain**  
**JE**  
**Kendujhar Sadar Block**

**Sabyasachi Pradhan**  
**AEE**  
**Kendujhar Sadar Block**

**Binod Chandra Panda**  
**BDO**  
**Kendujhar Sadar Block**