

Analysis

OD/361/3445/119307/385416/00069817 : Construction of CC Road from Indraprasth Munda Sahi to Banko

Block : Champua, Gram Panchayat : Sunaposi

Created By:KendujharChampuaBDO

Item 1
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	55	5500	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	536.41	53641	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	270.25	27025	0

Total Amount (a+b+c)	91876.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	6890.724
CONTRACTOR PROFIT @ 7.5% (+)	7407.5283
LABOUR CESS @ 1% (+)	1061.745723
Grand Total	107236.318023
Say For Unit 1 (Grand Total/100)	1072.36318023

Item 2
Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	567.52	1299.6208	233.931744
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	65	31.2	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	750	720	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	536.41	257.4768	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	601.51	577.4496	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	270.25	129.72	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	782.5	751.2	0

Total Amount (a+b+c)	5740.00348
Total GST (a)	233.931744
OVERHEAD CHARGES @ 7.5% (+)	448.0451418
CONTRACTOR PROFIT @ 7.5% (+)	481.648527435
LABOUR CESS @ 1% (+)	69.03628893235
Grand Total	6972.6651821673
Say For Unit 1 (Grand Total/1)	6972.6651821673

Item 3
Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0

LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	567.52	1833.0896	329.956128
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	65	29.25	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1370	1233	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	536.41	241.3845	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	601.51	541.359	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	270.25	121.6125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	782.5	704.25	0

Total Amount (a+b+c)	7310.56996
Total GST (a)	329.956128
OVERHEAD CHARGES @ 7.5% (+)	573.0394566
CONTRACTOR PROFIT @ 7.5% (+)	616.017415845
LABOUR CESS @ 1% (+)	88.29582960445
Grand Total	8917.8787900495
Say For Unit 1 (Grand Total/1)	8917.8787900495

Sudeshna Patra
JE
Champua Block

SABYASACHI NAYAK
AEE
Champua Block

KendujharChampuaBDO
BDO
Champua Block