

Analysis

OD/356/3397/118361/401460/00071522 : Const Of Tarini Bhogamandap At Samparu
Block : Dharmasala, Gram Panchayat : Samparu
Created By:Jyotirmaya Kar

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	406.21	40621	0

c) Royalty Rate Details					

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	309.35	30935	0
Total Amount (a+b+c)				84460.32	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)				6334.524	
CONTRACTOR PROFIT @ 7.5% (+)				6809.6133	
LABOUR CESS @ 1% (+)				976.044573	
Grand Total				98580.501873	
Say For Unit 1 (Grand Total/100)				985.80501873	

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	543.88	1245.4852	224.187336
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	940.6	902.976	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	406.21	194.9808	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	309.35	148.488	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	488.75	469.2	0

Total Amount (a+b+c)	5285.22023
-----------------------------	------------

Total GST (a)	224.187336
OVERHEAD CHARGES @ 7.5% (+)	413.20556745
CONTRACTOR PROFIT @ 7.5% (+)	444.19598500875
LABOUR CESS @ 1% (+)	63.668091184588
Grand Total	6430.4772096433
Say For Unit 1 (Grand Total/1)	6430.4772096433

Item 4

Masonry Brick Work (AR0603c): Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	4.3005	1720.2	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	543.88	365.48736	65.7877248
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	1.04474	417.896	0
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	406.21	113.7388	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	0	0	0
BRM340 : Cement	0.672	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	309.35	86.618	0
--	------	-------	--------	--------	---

Total Amount (a+b+c)	4913.943424
Total GST (a)	65.7877248
OVERHEAD CHARGES @ 7.5% (+)	373.47983616
CONTRACTOR PROFIT @ 7.5% (+)	401.490823872
LABOUR CESS @ 1% (+)	57.54701808832
Grand Total	5812.2488269203
Say For Unit 1 (Grand Total/1)	5812.2488269203

Item 5

Masonry Brick Work (AR0603ci): Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	4.3005	1720.2	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	543.88	365.48736	65.7877248
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	1.04474	417.896	0
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	406.21	113.7388	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	400	1000 Nos	0	0	0
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	309.35	86.618	0

Total Amount (a+b+c)	4946.943424
Total GST (a)	65.7877248
OVERHEAD CHARGES @ 7.5% (+)	375.95483616
CONTRACTOR PROFIT @ 7.5% (+)	404.151448872
LABOUR CESS @ 1% (+)	57.92837433832
Grand Total	5850.7658081703
Say For Unit 1 (Grand Total/1)	5850.7658081703

Item 6

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	309.35	139.2075	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	488.75	175.95	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	488.75	263.925	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	5728.978821146
Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	455.17570003995
CONTRACTOR PROFIT @ 7.5% (+)	489.31387754295
LABOUR CESS @ 1% (+)	70.134989114489

Grand Total	7083.6339005634
Say For Unit 1 (Grand Total/1)	7083.6339005634

Item 7

R.C.C. Work (AR0404Ab): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
LR008 : Sangi mulia	0.25	Per day	512	128	0
LR027 : Carpenter	0.25	Per day	562	140.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	198.296	2.6472516	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	198.296	0.60876872	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	309.35	139.2075	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	488.75	175.95	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	488.75	263.925	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

Total Amount (a+b+c)	6478.30765792
Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	511.375362798
CONTRACTOR PROFIT @ 7.5% (+)	549.72851500785
LABOUR CESS @ 1% (+)	78.794420484459
Grand Total	7958.2364689303
Say For Unit 1 (Grand Total/1)	7958.2364689303

Item 8

R.C.C. Work (AR0404Ac): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					

PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410d)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
LR008 : Sangi mulia	5.23875	Per day	512	2682.24	0
LR027 : Carpenter	5.23875	Per day	562	2944.1775	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	198.296	8.990542344	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	198.296	8.235034584	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	309.35	139.2075	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	488.75	175.95	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	488.75	263.925	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

Total Amount (a+b+c)	13704.972273938
Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	1053.3752089993
CONTRACTOR PROFIT @ 7.5% (+)	1132.3783496743
LABOUR CESS @ 1% (+)	162.30756345332
Grand Total	16393.063908785
Say For Unit 1 (Grand Total/1)	16393.063908785

Item 9

R.C.C. Work (AR0404Ag): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410a)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	1Mtr	51.87	322.714392	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	58374.79	2931.418504388	0
LR008 : Sangi mulia	3.05525	Per day	512	1564.288	0
LR027 : Carpenter	3.05525	Per day	562	1717.0505	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	198.296	15.201173064	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	198.296	9.9578698912	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	309.35	139.2075	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	488.75	175.95	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	488.75	263.925	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	0	0	0

Total Amount (a+b+c)	11968.468330443
Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	923.13741323724
CONTRACTOR PROFIT @ 7.5% (+)	992.37271923003
LABOUR CESS @ 1% (+)	142.2400897563

Grand Total	14366.249065387
Say For Unit 1 (Grand Total/1)	14366.249065387

Item 10

Concrete (AR0317): 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (new work)

Sub-Item of Work

2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.36	Per day	462	166.32	0
LR044 : Mason	0.1	Per day	612	61.2	0
BRM340 : Cement	0.1208	1 Qntl.	543.88	65.700704	11.82612672
BRM028 : Screened and washed sharp sand for mortar	0.0169	1 Cum	76.88	1.299272	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	1 Cum.	850.2	14.36838	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1208	1 Qntl.	24.787	2.9942696	0
BRM028 : Screened and washed sharp sand for mortar	0.0169	1 Cum	406.21	6.864949	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	1 Cum.	341.11	5.764759	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1208	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0169	1 Cum	309.35	5.228015	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	1 Cum.	488.75	8.259875	0

Total Amount (a+b+c)	338.0002236
Total GST (a)	11.82612672
OVERHEAD CHARGES @ 7.5% (+)	26.236976274
CONTRACTOR PROFIT @ 7.5% (+)	28.20474949455

LABOUR CESS @ 1% (+)	4.0426807608855
Grand Total	408.31075684944
Say For Unit 1 (Grand Total/1)	408.31075684944

Item 11

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	543.88	19.470904	3.50476272
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	24.787	0.8873746	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	406.21	6.09315	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	309.35	4.64025	0

Total Amount (a+b+c)	166.3648786
Total GST (a)	3.50476272
OVERHEAD CHARGES @ 7.5% (+)	12.740223099
CONTRACTOR PROFIT @ 7.5% (+)	13.695739831425
LABOUR CESS @ 1% (+)	1.9630560425042
Grand Total	198.26866029293
Say For Unit 1 (Grand Total/1)	198.26866029293

Item 12

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	543.88	23.38684	4.2096312
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	24.787	1.065841	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	406.21	7.31178	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	309.35	5.5683	0

Total Amount (a+b+c)				239.516601	
Total GST (a)				4.2096312	
OVERHEAD CHARGES @ 7.5% (+)				18.279467415	
CONTRACTOR PROFIT @ 7.5% (+)				19.650427471125	
LABOUR CESS @ 1% (+)				2.8165612708613	
Grand Total				284.47268835699	
Say For Unit 1 (Grand Total/1)				284.47268835699	

Item 13

Plastering (AR1027): 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.

Sub-Item of Work

6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.12	Per day	462	55.44	0

LR002 : Female mulia	0.05	Per day	462	23.1	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0372	1 Qntl.	543.88	20.232336	3.64182048
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	76.88	0.5766	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	24.787	0.9220764	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	406.21	3.046575	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	309.35	2.320125	0

Total Amount (a+b+c)	184.3177124
Total GST (a)	3.64182048
OVERHEAD CHARGES @ 7.5% (+)	14.096964966
CONTRACTOR PROFIT @ 7.5% (+)	15.15423733845
LABOUR CESS @ 1% (+)	2.1721073518445
Grand Total	219.38284253629
Say For Unit 1 (Grand Total/1)	219.38284253629

Item 14

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6192.55	65021.775	11703.9195

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM341 : Steel	10.5	1 Qntl.	42.622	447.531	0
----------------	------	---------	--------	---------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	71947.386
Total GST (a)	11703.9195
OVERHEAD CHARGES @ 7.5% (+)	6273.8479125
CONTRACTOR PROFIT @ 7.5% (+)	6744.3865059375
LABOUR CESS @ 1% (+)	966.69539918437
Grand Total	97636.235317622
Say For Unit 1 (Grand Total/10)	9763.6235317622

Item 15

Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work
Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2006	152.456	0
BRM340 : Cement	1.074	1 Qntl.	543.88	584.12712	105.1428816
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	76.88	16.1448	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	42.622	3.239272	0
BRM340 : Cement	1.074	1 Qntl.	24.787	26.621238	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	406.21	85.3041	0

BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	14.5102781	145.102781	0
--	----	-----------	------------	------------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	309.35	64.9635	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)	9908.598811
Total GST (a)	105.1428816
OVERHEAD CHARGES @ 7.5% (+)	751.030626945
CONTRACTOR PROFIT @ 7.5% (+)	807.35792396587
LABOUR CESS @ 1% (+)	115.72130243511
Grand Total	11687.851545946
Say For Unit 1 (Grand Total/10)	1168.7851545946

Item 16

Flooring (AR0817b): Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	405.2	4052	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR044 : Mason	3.25	Per day	612	1989	0
BRM340 : Cement	1.375	1 Qntl.	543.88	747.835	134.6103
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	14.5102781	145.102781	0
BRM340 : Cement	1.375	1 Qntl.	24.787	34.082125	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	406.21	60.9315	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	309.35	46.4025	0

Total Amount (a+b+c)	8588.385906
Total GST (a)	134.6103
OVERHEAD CHARGES @ 7.5% (+)	654.22471545
CONTRACTOR PROFIT @ 7.5% (+)	703.29156910875
LABOUR CESS @ 1% (+)	100.80512490559
Grand Total	10181.317615464
Say For Unit 1 (Grand Total/10)	1018.1317615464

Item 17
Painting (AR0918cb): Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)
Sub-Item of Work Finishing wall two coats with weather coat with one coat waterbound Primer

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	193	24.125	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901di)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	155.6	14.054193548387	0

LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.42622	0.0532775	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.42622	0.038497290322581	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

Total Amount (a+b+c)	158.62890382258
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11.897167786694
CONTRACTOR PROFIT @ 7.5% (+)	12.789455370696
LABOUR CESS @ 1% (+)	1.8331552697997
Grand Total	185.14868224977
Say For Unit 1 (Grand Total/1)	185.14868224977

Item 18

Iron Work (AR1704): Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

Sub-Item of Work

Iron Doors and windows fixing

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6192.55	3145.8154	566.246772
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR047 : Fitter	1	Per day	612	612	0
LR026 : Black smith	1	Per day	562	562	0
LR046 : Blacksmith	0.75	Per day	612	459	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	42.622	21.651976	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	0	0	0

Total Amount (a+b+c)	7375.967376				
Total GST (a)	566.246772				
OVERHEAD CHARGES @ 7.5% (+)	595.6660611				
CONTRACTOR PROFIT @ 7.5% (+)	640.3410156825				
LABOUR CESS @ 1% (+)	91.782212247825				
Grand Total	9270.0034370303				
Say For Unit 1 (Grand Total/0.508)	18248.038261871				

SANTOSHI PANDA
JE
Dharmasala Block

LINGARAJ PANDA
AEE
Dharmasala Block

Jyotirmaya Kar
BDO
Dharmasala Block