

Analysis

OD/361/3450/119431/385314/00067534 : Repair and Maintenance of Anganwadi Centre at Sanahundula -1

Block : Jhumpura, Gram Panchayat : Nischintpur

Created By:KendujharJhumpuraBDO

Item 1

Plastering (AR1017): 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

20mm thick cement Plaster in CM (1:4) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.0744	1 Qntl.	567.52	42.223488	7.60022784
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	65	1.365	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0744	1 Qntl.	48.567	3.6133848	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	1137.91	23.89611	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0744	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	50.25	1.05525	0

Total Amount (a+b+c)	272.9532328
Total GST (a)	7.60022784
OVERHEAD CHARGES @ 7.5% (+)	21.041509548
CONTRACTOR PROFIT @ 7.5% (+)	22.6196227641
LABOUR CESS @ 1% (+)	3.242145929521
Grand Total	327.45673888162
Say For Unit 1 (Grand Total/1)	327.45673888162

BABUL KUMAR BEHERA
JE
Jhumpura Block

SIDA MAJHEE
AEE
Jhumpura Block

KendujharJhumpuraBDO
BDO
Jhumpura Block