

Analysis

**OD/366/3517/120494/427919/00065193 : Repair and maintenance of Upper Primary School
Majhiguda
Block : Nabarangpur, Gram Panchayat : Mantriguda
Created By:SUNIL KHORA**

Item 1

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	40.25	4025	0

Total Amount (a+b+c)

51040.32

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

3828.024

CONTRACTOR PROFIT @ 7.5% (+)

4115.1258

LABOUR CESS @ 1% (+)

589.834698

Grand Total

59573.304498

Say For Unit 1 (Grand Total/100)

595.73304498

Item 2

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	561	1284.69	231.2442
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.13	36.5424	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	40.25	19.32	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	149.5	143.52	0

Total Amount (a+b+c)	4904.04708
Total GST (a)	231.2442
OVERHEAD CHARGES @ 7.5% (+)	385.146846
CONTRACTOR PROFIT @ 7.5% (+)	414.03285945
LABOUR CESS @ 1% (+)	59.3447098545
Grand Total	5993.8156953045
Say For Unit 1 (Grand Total/1)	5993.8156953045

Item 3
Flooring (AR0802i): 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.
Sub-Item of Work 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.14	Per day	462	64.68	0

LR002 : Female mulia	0.22	Per day	462	101.64	0
LR044 : Mason	0.13	Per day	612	79.56	0
BRM340 : Cement	0.0858	1 Qntl.	561	48.1338	8.664084
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	76.13	0.91356	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	1396.62	32.12226	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	30.732	2.6368056	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	341.11	4.09332	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	341.11	7.84553	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	40.25	0.483	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	149.5	3.4385	0

Total Amount (a+b+c)	345.5467756
Total GST (a)	8.664084
OVERHEAD CHARGES @ 7.5% (+)	26.56581447
CONTRACTOR PROFIT @ 7.5% (+)	28.55825055525
LABOUR CESS @ 1% (+)	4.0933492462525
Grand Total	413.4282738715
Say For Unit 1 (Grand Total/1)	413.4282738715

Item 4

Roofing (AR1132i): Supplying, fitting & fixing of G.C.I. Sheet (0.40mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge

Sub-Item of Work

Supplying, feeting & fixing of G.C.I. Sheet (0.40mm thick) in roof drilling hole in wind ties

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM150 : G.C.I. Sheet 0.40mm thick	9.3	1 Sqm.	333.12	3098.016	0
LR001 : Male mulia	2	Per day	462	924	0
LR047 : Fitter	1	Per day	612	612	0
LR045 : Carpenter	0.5	Per day	612	306	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM150 : G.C.I. Sheet 0.40mm thick	9.3	1 Sqm.	1.0110828	9.40307004	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM150 : G.C.I. Sheet 0.40mm thick	9.3	1 Sqm.	0	0	0

Total Amount (a+b+c)	4949.41907004				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	371.206430253				
CONTRACTOR PROFIT @ 7.5% (+)	399.04691252197				
LABOUR CESS @ 1% (+)	57.19672412815				
Grand Total	5776.8691369431				
Say For Unit 1 (Grand Total/9.3)	621.16872440249				

Item 5
Painting (AR0918cb): Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)
Sub-Item of Work Finishing wall two coats with weather coat with one coat waterbound Primer

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901di)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.30732	0.038415	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.30732	0.027757935483871	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

Total Amount (a+b+c)	159.13685841935				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	11.935264381452				
CONTRACTOR PROFIT @ 7.5% (+)	12.83040921006				
LABOUR CESS @ 1% (+)	1.8390253201087				
Grand Total	185.74155733098				
Say For Unit 1 (Grand Total/1)	185.74155733098				

Item 6
Iron Work (AR1703): Iron work wrought and put up in trusses and record racks including all cost of labour, material, machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.
Sub-Item of Work Iron work wrought and put up in trusses and record racks

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6183.17	3141.05036	565.3890648
LR001 : Male mulia	2.5	Per day	462	1155	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR026 : Black smith	1.25	Per day	562	702.5	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	30.732	15.611856	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM341 : Steel	0.508	1 Qntl.	0	0	0
----------------	-------	---------	---	---	---

Total Amount (a+b+c)	6088.162216
Total GST (a)	565.3890648
OVERHEAD CHARGES @ 7.5% (+)	499.01634606
CONTRACTOR PROFIT @ 7.5% (+)	536.4425720145
LABOUR CESS @ 1% (+)	76.890101988745
Grand Total	7765.9003008632
Say For Unit 1 (Grand Total/0.508)	15287.20531666

Item 7

Masonry Brick Work (AR0603ei): Brickwork with C.B. Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

C.B. Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
BRM002 : Well burnt clamp burnt bricks (23 Cm. x 11Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm ² with dimensional tolerance ± 8 percent.	400	1000 Nos	3.86472	1545.888	0
LR001 : Male mulia	2.96	Per day	462	1367.52	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	561	376.992	67.85856
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.13	21.3164	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM002 : Well burnt clamp burnt bricks (23 Cm. x 11Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm ² with dimensional tolerance ± 8 percent.	400	1000 Nos	0.8091	323.64	0
BRM340 : Cement	0.672	1 Qntl.	30.732	20.651904	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	341.11	95.5108	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM002 : Well burnt clamp burnt bricks (23 Cm. x 11Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm2 with dimensional tolerance \pm 8 percent.	400	1000 Nos	0.04025	16.1	0
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	40.25	11.27	0

Total Amount (a+b+c)	4680.869104
Total GST (a)	67.85856
OVERHEAD CHARGES @ 7.5% (+)	356.1545748
CONTRACTOR PROFIT @ 7.5% (+)	382.86616791
LABOUR CESS @ 1% (+)	54.8774840671
Grand Total	5542.6258907771
Say For Unit 1 (Grand Total/1)	5542.6258907771

Item 8

Plastering (AR1004): 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	561	20.0838	3.615084
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.13	1.14195	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	30.732	1.1002056	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	341.11	5.11665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	40.25	0.60375	0

Total Amount (a+b+c)	162.1663556
Total GST (a)	3.615084
OVERHEAD CHARGES @ 7.5% (+)	12.43360797
CONTRACTOR PROFIT @ 7.5% (+)	13.36612856775
LABOUR CESS @ 1% (+)	1.9158117613775
Grand Total	193.49698789913
Say For Unit 1 (Grand Total/1)	193.49698789913

**SK MURSHID
JE
Nabarangpur Block**

**SURYA NARAYAN BEHERA
AEE
Nabarangpur Block**

**SUNIL KHORA
BDO
Nabarangpur Block**