

Analysis

**OD/353/3360/117508/413471/00071540 : Construction of CC Road with drain at Janabasati
sahi Danigain
Block : Mohona, Gram Panchayat : Kattama
Created By:Rajiv Das**

Item 1
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	705.67	70567	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	279.25	27925	0

Total Amount (a+b+c)	111396.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	8354.724
CONTRACTOR PROFIT @ 7.5% (+)	8981.3283
LABOUR CESS @ 1% (+)	1287.323723
Grand Total	130019.696023
Say For Unit 1 (Grand Total/100)	1300.19696023

Item 2
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	569.86	1304.9794	234.896292
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	33.11	75.8219	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	679.63	326.2224	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	705.67	677.4432	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	279.25	134.04	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	269.5	258.72	0

Total Amount (a+b+c)	5672.5293
Total GST (a)	234.896292
OVERHEAD CHARGES @ 7.5% (+)	443.0569194
CONTRACTOR PROFIT @ 7.5% (+)	476.286188355
LABOUR CESS @ 1% (+)	68.26768699755
Grand Total	6895.0363867526
Say For Unit 1 (Grand Total/1)	6895.0363867526

Item 3
R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc
Sub-Item of Work R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0

BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.570465023
CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972
LABOUR CESS @ 1% (+)	24.741232485627
Grand Total	2498.8644810484
Say For Unit 1 (Grand Total/10)	249.88644810484

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	569.86	1840.6478	331.316604

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	33.11	106.9453	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	705.67	317.5515	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	679.63	611.667	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	279.25	125.6625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	269.5	242.55	0

Total Amount (a+b+c)	7043.9381
Total GST (a)	331.316604
OVERHEAD CHARGES @ 7.5% (+)	553.1441028
CONTRACTOR PROFIT @ 7.5% (+)	594.62991051
LABOUR CESS @ 1% (+)	85.2302871731
Grand Total	8608.2590044831
Say For Unit 1 (Grand Total/1)	8608.2590044831

Item 5
Earth Work (AR0103aa): Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume in foundation and plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.3m in depth and as per specification approved by the department
Sub-Item of Work Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume in foundation and plinth within 50m. Initial lead and 1.5m

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	40.236	Per day	462	18589.032	0

LR001 : Male mulia	40.236	Per day	462	18589.032	0
Total Amount (a+b+c)				37178.064	
Total GST (a)				0	
OVERHEAD CHARGES @ 7.5% (+)				2788.3548	
CONTRACTOR PROFIT @ 7.5% (+)				2997.48141	
LABOUR CESS @ 1% (+)				429.6390021	
Grand Total				43393.5392121	
Say For Unit 1 (Grand Total/100)				433.935392121	

Sunil Kumar Ratha
JE
Mohona Block

Asis Kumar Satapathy
AEE
Mohona Block

Rajiv Das
BDO
Mohona Block