

Analysis

**OD/346/3309/116321/393686/00074057 : Construction of CC road from incomplete CC road to Bhaskar Senapati House, Senapati Sahi
Block : Soro, Gram Panchayat : Manipur
Created By:Satyanath Naik**

Item 1
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	963.11	96311	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	442.25	44225	0

Total Amount (a+b+c)	153440.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11508.024
CONTRACTOR PROFIT @ 7.5% (+)	12371.1258
LABOUR CESS @ 1% (+)	1773.194698
Grand Total	179092.664498
Say For Unit 1 (Grand Total/100)	1790.92664498

Item 2
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	537.2	1230.188	221.43384
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	27.165	62.20785	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	963.11	462.2928	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	406.21	389.9616	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	552.5	530.4	0

Total Amount (a+b+c)	5782.63265				
Total GST (a)	221.43384				
OVERHEAD CHARGES @ 7.5% (+)	450.30498675				
CONTRACTOR PROFIT @ 7.5% (+)	484.07786075625				
LABOUR CESS @ 1% (+)	69.384493375062				
Grand Total	7007.8338308813				
Say For Unit 1 (Grand Total/1)	7007.8338308813				

Item 3
R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc
Sub-Item of Work R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0

BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.570465023
CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972
LABOUR CESS @ 1% (+)	24.741232485627
Grand Total	2498.8644810484
Say For Unit 1 (Grand Total/10)	249.88644810484

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	537.2	1735.156	312.32808

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	27.165	87.74295	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	963.11	433.3995	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	406.21	365.589	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	552.5	497.25	0

Total Amount (a+b+c)	7117.06395
Total GST (a)	312.32808
OVERHEAD CHARGES @ 7.5% (+)	557.20440225
CONTRACTOR PROFIT @ 7.5% (+)	598.99473241875
LABOUR CESS @ 1% (+)	85.855911646687
Grand Total	8671.4470763154
Say For Unit 1 (Grand Total/1)	8671.4470763154

Item 5
Earth Work (AR0101aa): Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum
Sub-Item of Work Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	19.2	Per day	462	8870.4	0
LR001 : Male mulia	19.2	Per day	462	8870.4	0

Total Amount (a+b+c)	17740.8
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1330.56
CONTRACTOR PROFIT @ 7.5% (+)	1430.352
LABOUR CESS @ 1% (+)	205.01712
Grand Total	20706.72912
Say For Unit 1 (Grand Total/100)	207.0672912

Item 6

Road Work (AR1304): Flank dressing to proper camber and as per direction of Engineer-in-charge.

Sub-Item of Work

Flank dressing to proper camber and as per direction of Engineer-in-charge.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.12	Per day	462	55.44	0

Total Amount (a+b+c)	55.44
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	4.158
CONTRACTOR PROFIT @ 7.5% (+)	4.46985
LABOUR CESS @ 1% (+)	0.6406785
Grand Total	64.7085285
Say For Unit 1 (Grand Total/9.3)	6.9579062903226

Taruna Kumar Nandi
JE
Soro Block

Nirmala Kanta Parida
AEE
Soro Block

Satyanath Naik
BDO
Soro Block