

Analysis

**OD/350/3338/116983/400213/00072557 : Construction of Paver block road infront of Anthua
Gopala Temple, Mallick Sahi
Block : Kantapada, Gram Panchayat : Postal
Created By: Swapnita Nayak**

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

1787.94

CONTRACTOR PROFIT @ 7.5% (+)

1922.0355

LABOUR CESS @ 1% (+)

275.491755

Grand Total

27824.667255

Say For Unit 1 (Grand Total/100)

278.24667255

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	406.21	40621	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	227.25	22725	0

Total Amount (a+b+c)	76250.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	5718.774				
CONTRACTOR PROFIT @ 7.5% (+)	6147.68205				
LABOUR CESS @ 1% (+)	881.1677605				
Grand Total	88997.9438105				
Say For Unit 1 (Grand Total/100)	889.979438105				

Item 3
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	538.98	1234.2642	222.167556
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	946.4	908.544	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	406.21	194.9808	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	1229.91	1180.7136	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	227.25	109.08	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	158.5	152.16	0

Total Amount (a+b+c)	5789.98128
Total GST (a)	222.167556
OVERHEAD CHARGES @ 7.5% (+)	450.9111627
CONTRACTOR PROFIT @ 7.5% (+)	484.7294999025
LABOUR CESS @ 1% (+)	69.477894986025
Grand Total	7017.2673935885
Say For Unit 1 (Grand Total/1)	7017.2673935885

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	538.98	1740.9054	313.362972
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1375	1237.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1229.91	1106.919	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	227.25	102.2625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	158.5	142.65	0

Total Amount (a+b+c)	7154.25176
Total GST (a)	313.362972
OVERHEAD CHARGES @ 7.5% (+)	560.0711049
CONTRACTOR PROFIT @ 7.5% (+)	602.0764377675
LABOUR CESS @ 1% (+)	86.297622746675
Grand Total	8716.0598974142
Say For Unit 1 (Grand Total/1)	8716.0598974142

Item 5

miscellaneous (ARM287): Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.

Sub-Item of Work

Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.03	1 Cum	71.94	2.1582	0
BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	1 Sqm	608.4	608.4	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.03	1 Cum	406.21	12.1863	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.03	1 Cum	227.25	6.8175	0

Total Amount (a+b+c)	629.562
Total GST (a)	0
Grand Total	8716.0598974142
Say For Unit 1 (Grand Total/1)	8716.0598974142

Item 6

Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	538.98	362.19456	65.1950208
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.0273	1759.555	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	30.732	20.651904	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	406.21	113.7388	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	1.01135	353.9725	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	227.25	63.63	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	0	0	0

Total Amount (a+b+c)	4867.089164
Total GST (a)	65.1950208
OVERHEAD CHARGES @ 7.5% (+)	369.92131386
CONTRACTOR PROFIT @ 7.5% (+)	397.6654123995
LABOUR CESS @ 1% (+)	56.998709110595

Grand Total	5756.8696201701
Say For Unit 1 (Grand Total/1)	5756.8696201701

Usharani Panda
JE
Kantapada Block

DHANANJAY SAMAL
AEE
Kantapada Block

Swapnita Nayak
BDO
Kantapada Block